

I-15 TROPICANA GEOTECHNICAL DATA REPORT

PREPARED FOR:



NEVADA DEPARTMENT OF TRANSPORTATION

PREPARED BY:

CA GROUP, INC.
2785 S. RAINBOW BOULEVARD
LAS VEGAS, NV 89146



SEPTEMBER 2019



Technical Memorandum

TO: Kyle Jermstad, NDOT

DATE: September 2019


FROM: Ravee Raveendra, P.E., Jacobs and Greg Fischer, Jacobs

SUBJECT: I-15 Tropicana Geotechnical Data Report


COPIES: Jack Sjostrom, CA Group; Jeff Lerud, NDOT; Mike Griswold, NDOT; Mike Cooper, Jacobs; Ravee Raveendra, Jacobs; Ken Gilbreth, Jacobs; Sriram Bala/CA Group

I. Acknowledgements

The following individuals have participated in the preparation of the I-15 Tropicana Geotechnical Data Report or have completed quality review or both.



Greg Fischer
Geotechnical Engineer



Greg Warren
Senior Geologist



Ravee Raveendra, P.E.
Geotechnical Task Lead



Curt Basnett, P.E.
Senior Reviewer



II. Introduction

A. General

The Nevada Department of Transportation (NDOT) is proposing to reconstruct the I-15 and Tropicana Avenue interchange and other associated improvements in Las Vegas, Nevada, from just north of the Hacienda Avenue overpass of I-15 on the south to the south side of the Flamingo Avenue overpass on the north. The project consists of reconstructing a tight diamond interchange at Tropicana Avenue, adding thru and turning lanes for improved capacity and operations of Tropicana Avenue, and realignment of the flyover from southbound I-15 to eastbound Tropicana Avenue. The project includes new high-occupancy vehicle (HOV) drop ramps at Harmon Avenue with signalized T-intersections at the ramp termini. There will be right-of-way acquisitions along Tropicana Avenue to accommodate additional thru lanes along Tropicana Avenue, turn lanes at the interchange, new RTC bus turnouts, widening of the ramps, and realignment of the two-lane flyover. Jacobs is providing engineering design services for the proposed project. A site location map is presented on Figure 1-1.

This Geotechnical Data Report includes the geotechnical exploration data, in situ testing data, and laboratory test results from the geotechnical investigation for the I-15 Tropicana Interchange Project in 2019. This report was prepared to support the design of the proposed I-15 project.

B. Scope of Work

The scope of work for the Geotechnical Data Report includes the following:

- Review readily available existing geotechnical information and geologic maps.
- Perform drilling, sampling, and logging of 10 borings during the I-15 Tropicana Interchange field exploration program.
- Conduct Refraction Microtremor (ReMi) testing to measure the average shear wave velocity within the upper 100 feet of native ground to establish the seismic site class.
- Conduct laboratory testing of selected samples to characterize the subsurface materials.
- Prepare this Geotechnical Data Report.

C. Limitations

This Geotechnical Data Report was prepared for the exclusive use of NDOT and the Jacobs design team for specific application to the Design-Build procurement development of the I-15 Tropicana Interchange Project. This report has been prepared in accordance with NDOT's current geotechnical practice. No other warranty, express or implied, is made.

The subsurface conditions described in this report are based on data obtained from published information and borings advanced by Cascade Drilling. The soil borings indicate subsurface conditions only at specific locations at the time of exploration and only within the depths explored. They do not necessarily reflect subsurface variations that could exist between such locations or between samples, or changes that could take place with time. Jacobs is not responsible for any claims, damages, or liability associated with the reinterpretation or reuse of the subsurface data in this report by others.

III. Project Description

The project proposes to reconstruct the entirety of the I-15 and Tropicana Avenue interchange to improve operations, capacity, and safety. The project will also introduce an HOV interchange at the existing Harmon Avenue overpass of I-15, providing an additional access point to I-15 for HOVs and reducing congestion in the Tropicana interchange area. The project construction limits are anticipated to stretch from just north of the Hacienda Avenue overpass of I-15 on the south to the south side of the Flamingo Avenue overpass on the north.

In general, the roadway improvements consist of:

- Pavement widening
- Drainage improvements
- Structure and roadway demolition
- New roadway bridges over I-15 and on three of the four existing Tropicana ramps
- New ramps for HOVs
- Updated signing, lighting, striping, and intelligent transportation system components

The Tropicana interchange was originally constructed in 1996 as the main interstate connection to McCarran International Airport. Commuter and corridor trips are expected to increase significantly as more development occurs in the interchange vicinity and construction of the Las Vegas Raiders stadium is completed.

IV. Geologic Conditions and Seismicity

A. Regional Geology

The Las Vegas Valley is one of the many structural basins formed during the late Tertiary (approximately 20 million years ago) continental extension of what is now the southwestern United States and northern Mexico. This continental extension formed an immense region of alternating, generally north-south-trending faulted mountains (ranges) and flat valley floors (basins) known as the Basin and Range Province. The Basin and Range Province includes the state of Nevada, and extends from southern Oregon to western Texas and into northern Mexico (Liu, 2001).

The tectonic history of Las Vegas Valley is complex. In general, the valley formed by southwest-northeast extension and northwest-southeast elongation that created pull-apart basins and a structural low between the Spring Mountains (to the west-southwest), the Sheep and Las Vegas Ranges (to the northeast), and Frenchman Mountain (to the east-southeast) (Page et al., 2005). In general, down-dropping of the valley occurred along numerous strike-slip and normal faults along the basin margins, as well as many intra-valley normal faults.

During continued down-dropping of the basin, sediment derived from the surrounding mountains gradually filled, and continues to fill, Las Vegas Valley. The thickness of the sedimentary fill within the Las Vegas basin is on the order of 10,000 to 13,000 feet, and consists of Miocene-age (approximately 20 to 5 million years) through Holocene-age (less than 10,000 years) lacustrine, fluvial and alluvial fan, paludal, and spring deposits (Page et al., 2005). Generally, coarser-grained deposits are located near the base of the mountains, transitioning to finer-grained deposits toward the middle of the valley.

B. Local Geology

Based on the geologic maps of Page et al. (2005) and Matti et al. (1987), and our recent site reconnaissance and subsurface exploration, the project site is underlain by young fan and youngest fan alluvium (Qay and Qayy) in the near surface, and by what has been interpreted as undivided fine-grained sediments of the Las Vegas Valley (QTs) at depth. Since the various sedimentary units described herein are very similar in their geologic characteristics (such as age, lithology, etc.), the units have been combined into a single classification of “Native Deposits” for the purposes of this report. A geologic map is presented on Figure 2-1. In addition to these geologic units, the project site is underlain by artificial fills consisting of silty and clayey sand with gravel associated with previous construction along I-15 and adjacent improvements.

C. Faulting and Seismicity

1. Faulting

Based on the geologic reports and maps reviewed, active faults (evidence of displacement during the Holocene) have not been mapped transecting the project alignment. Prominent faults in the area surrounding the project alignment include numerous splays of the Las Vegas Valley Fault System (LVVFS - includes the Eglington, Cashman, Valley View, and Decatur segments), the Frenchman Mountain Fault, and the Las Vegas Valley Shear Zone (LVVSZ).

2. Las Vegas Valley Fault System

Faults of the LVVFS have been mapped in the vicinity of the project alignment (see Figure 2-1). The LVVFS consists of numerous named and unnamed, mostly normal, intra-valley fault strands that form a zone approximately 18.6 miles long and up to 6.8 miles wide. Fault strands in the southern portion of the LVVFS generally strike north to northwest and dip eastward. In the northern portion of the LVVFS, fault strands generally strike north to northeast and dip eastward. Scarps of the LVVFS have been observed within surficial deposits and range in height from a few feet to 100 feet (dePolo et al., 2006).

Prominent faults of the LVVFS include the Valley View, Decatur, Eglington and Cashman segments. Figure 2-1 shows the location of these faults relative to the project alignment.

The nearest mapped faults to the project site are unnamed splays of the LVVFS located a little less than 1.0 mile to the northwest, northeast, and west of the project alignment. Based on the geologic reports and maps reviewed, these faults are not considered to be active during the Holocene epoch.

3. Frenchman Mountain Fault

The Frenchman Mountain Fault is located approximately 8 miles east of the project alignment, near the western base of Frenchman Mountain. The Frenchman Mountain Fault is a normal fault, approximately 13.5 miles long, and consists of several nonaligned short segments cutting various alluvial fans ranging in age from middle Pleistocene to early Holocene (Page et al., 2005). A steep gravity gradient west of the range front fault coincides with the entire Frenchman Mountain piedmont, indicating that the main range-bounding fault is located approximately 1 mile west of the range front (Page et al., 2005).

4. Las Vegas Valley Shear Zone

The LVVSZ is a series of northwest-trending faults that can be traced for approximately 93 miles, from Mercury, Nevada, southeast to the Lake Mead area (Page et al., 2005). The nearest strand of the LVVSZ is approximately 4 miles to the northeast of the northern portion of the project alignment. The LVVSZ has approximately 30 miles of right-lateral strike-slip displacement (Page et al., 2005). Due to concealment of the LVVSZ by thick Tertiary and Quaternary basin fill, its geometry and location are based primarily on geophysical studies, where the LVVSZ is delineated in the subsurface by a steep gravity gradient (Langenheim et al., 2005). Page et al. (2005) interpreted that a strand of the LVVSZ cuts across the valley and is aligned with the Frenchman Mountain Fault segment that bounds the southern margin of Frenchman Mountain. As a result, it has been inferred that the LVVSZ has played a significant role in the tectonic development of Las Vegas Valley. The LVVSZ formed during episodes of extensional faulting in Cenozoic time. Paleomagnetic data, along with other structural data, bracket the principal period of movement along the LVVSZ at between 14 and 8.5 million years. As such, the LVVSZ is not considered seismically active.

D. Groundwater

Groundwater was encountered in the project explorations approximately 16 to 34 feet below the native ground surface. These results generally agree with groundwater information provided by the Las Vegas Valley Groundwater Management Program (<http://www.lasvegasgmp.com>). Fluctuations in the groundwater level and soil moisture content variations should be anticipated during and after the rainy season. Irrigation of landscaped areas, nearby construction, and numerous other human-made and natural influences also could cause a fluctuation in local groundwater levels.

E. Subsidence

Historical land subsidence in the Las Vegas Valley has been caused primarily by groundwater withdrawal exceeding groundwater recharge. The central portion of the Las Vegas Valley has a high content of fine-grained sediments (silt and clay) that makes it conducive to consolidation upon water extraction. Geologic, hydrogeologic, and topographic investigations conducted throughout the Las Vegas Valley show that the pattern of valleywide subsidence occurs as one large subsidence bowl composed of four principal and localized subsidence zones: the Northwest, North Las Vegas, Central (Downtown Las Vegas), and Southern (Las Vegas Strip) bowls (Bell et al., 1992; Bell, 1981). Initially, the location of the subsidence bowls was believed to be directly related to heavy groundwater extraction in these areas, and movement was inferred to be uniformly distributed about these extraction areas. However, it was later discovered that the location of the subsidence bowls did not correspond exactly to areas of heavy groundwater extraction and that subsidence is occurring in a series of elongated bowls that are each generally bounded by pre-existing Quaternary faults, which act as subsidence movement barriers.

The project alignment is located near the middle of the Central subsidence bowl as defined by Bell et al. (2001 and 2002). The amount of historical subsidence in the vicinity of the alignment is on the order of 23 to 34 inches (from 1935 to 2000). Since 1991, subsidence in the vicinity of the project alignment has declined and is approximately 0.2 inch per year (Bell et al., 2002).

V. Subsurface Conditions

A. Field Investigation

Ten soil borings were drilled between March 18 and April 19, 2019, along the project corridor to provide subsurface data. The borings were advanced using 8-inch outside diameter (O.D.) hollow-stem auger drilling techniques by Cascade Drilling under subcontract to BEC Environmental and Jacobs, using a truck-mounted CME-85 drill rig equipped with a 140-pound automatic hammer falling freely for 30 inches. Energy measurement calibration of the hammer was performed by SPT CAL under subcontract to Cascade Drilling. The automatic hammer used for the CME-85 drill rig had an estimated efficiency of about 70 percent. The hammer energy measurement (hammer calibration) report is provided in Appendix A.

The boring information is summarized in Table 4-1. Boring location maps are presented in Appendix B, and the boring logs are presented in Appendix C.

Table 4-1. Summary of Geotechnical Field Exploration
I-15 Tropicana

Soil Boring Number	Latitude	Longitude	Ground Surface Elevation ^a (feet)	Exploration Depth (feet)	Groundwater Table Elevation (feet)
BH-19-01	N36°05'56.60936"	W115°10'51.73387"	2063.8	101.5	2046.5
BH-19-02	N36°05'59.34843"	W115°10'52.39264"	2066.2	101.5	2047.7
BH-19-03	N36°06'02.56404"	W115°10'52.85753"	2074.1	101.4	2040.3
BH-19-04	N36°06'06.10614"	W115°10'52.65259"	2071.9	121.5	2041.9
BH-19-05	N36°06'01.02693"	W115°10'50.30150"	2055.3	121.5	2035.5
BH-19-06	N36°06'03.17881"	W115°10'47.41719"	2070.7	101.5	2037.8
BH-19-07	N36°06'06.23381"	W115°10'48.36073"	2061.4	100.2	2035.1
BH-19-08	N36°06'00.85298"	W115°10'44.98826"	2052.4	120.3	2036.4
BH-19-09	N36°06'02.72498"	W115°10'43.92813"	2061.5	101.4	2035.2
BH-19-10	N36°06'28.38353"	W115°10'50.20417"	2039.4	101.5	2019.9

^a Elevations are based on North American Vertical Datum of 1988 (NAVD 88).

As shown on the boring logs in Appendix C, standard penetration tests and pocket penetrometer readings were performed. Soil samples were collected by 1.5-inch inside diameter (I.D.) split-barrel sampler, 2.5-inch I.D. modified California sampler, and 3-inch O.D. thin-walled (Shelby) tube.

The sampling procedures generally followed ASTM International (ASTM) D1586, Standard Test Method for Standard Penetration Test (SPT) and Split-Barrel Sampling of Soils (ASTM, 2019). The borings were logged by a geologist or engineer with NOVA Geotechnical and Inspection Services (NOVA). Each soil sample collected was described using the Unified Soil Classification System (USCS) in accordance with ASTM D2487 and D2488. Following the drilling, sampling, and logging, the borings were backfilled with bentonite cement grout in accordance with state regulations.

B. Laboratory Tests

Bulk disturbed and relatively undisturbed soil samples were collected, and selected samples were tested in the laboratory. Laboratory testing was assigned by Jacobs and performed by NOVA Geotechnical and Terracon Consultants, Inc. (Terracon) under subcontract to BEC Environmental and Jacobs. Laboratory testing was performed to aid in the field classification of the samples collected and to provide the geotechnical engineering properties of subsurface materials. Tests included moisture content, in situ density, particle-size analysis, Atterberg limits, direct shear, unconsolidated undrained triaxial shear, one-dimensional consolidation, R-value, and corrosion tests. Testing was completed in accordance with applicable American Association of State Highway and Transportation Officials (AASHTO), ASTM, and NDOT standards. The laboratory tests performed are summarized in Table 4-2. Test results are presented in Appendix D.

Table 4-2. Summary of Laboratory Test Methods

I-15 Tropicana

Laboratory Test	Test Method
Moisture Content	AASHTO T-265
In-situ Density	ASTM D7263
Particle-Size Analysis	NDOT T206
Atterberg Limits	NDOT T210, T211, and T212
Direct Shear	ASTM D3080
Unconsolidated Undrained Triaxial	AASHTO T-296
One-Dimensional Consolidation	ASTM D2435
R-value	NDOT T115D
Resistivity	AASHTO T-288
pH	AASHTO T-289
Sulfates	AASHTO T-290
Chlorides	ASTM D4327

C. Refraction Microtremor Seismic Survey

NOVA conducted ReMi geophysical surveys in April 2019 at two locations along the project corridor, Tropicana Avenue/I-15 and Harmon Avenue/I-15. The data were provided to SubTerraSeis for shear wave analysis. The objectives of the geophysical investigation included providing shear-wave velocity profiles to a depth of 100 feet for seismic site class determination. Seismic surface wave analysis techniques, in particular the linear-array passive microtremor method, were used to model shear-wave velocity. The ReMi survey report is presented in Appendix E.

D. Subsurface Conditions

1. Soil

Based on the data from the soil borings advanced for the project, the subsurface materials generally consist of embankment fill material (artificial fill) and native clayey soils. Fill material encountered in the soil borings consists of brown, dense to very dense, moist, silty and clayey sands and gravels. The native soil below the fill generally consists of interbedded, soft to hard, lean to fat clays with some sand and gravel locally; medium to very dense clayey and silty sands with some gravel locally; and some clayey gravel. Few hard caliche layers and cemented lenses exist locally. Detailed subsurface conditions are presented in the boring logs in Appendix C.

2. Bedrock

Bedrock was not encountered during the subsurface explorations. As discussed in Section IV.A of this report, soil sediments in the project vicinity are 10,000 to 13,000 feet thick.

E. Groundwater

Groundwater was encountered in the project explorations approximately 16 to 34 feet below the ground surface at elevation 2020 to 2048 feet (NAVD 88).

VI. References

- ASTM International (ASTM). 2019. *Annual Book of Standards*. West Conshohocken, Pennsylvania.
- Bell, J.W. 1981. *Subsidence in Las Vegas Valley*. Nevada Bureau of Mines and Geology Bulletin 95. 84 pp.
- Bell, J.W., J.G Price, and M.D. Mifflin. 1992. Subsidence-induced Fissuring Along Preexisting Faults in Las Vegas Valley, Nevada. In *Association of Engineering Geologists, Proceedings of the 35th Annual Meeting*, Los Angeles. pp. 66-75.
- Bell, J.W., A. Ramelli, and C.M. dePolo. 2001. *Las Vegas Valley 1998 Subsidence Report*, Nevada Bureau of Mines and Geology. Open-File Report 01-4.
- Bell, J.W., A. Falk, A.R. Ramelli, and G. Blewitt. 2002. Land Subsidence in Las Vegas, Nevada, 1935-2000: New Geodetic Data Show Evolution, Revised Spatial Patterns, and Reduced Rates. *Environmental & Engineering Geoscience*. Vol. VIII, No. 3. pp. 155-174. August.
- dePolo, C.M., J.W. Bell, S. Boron, D.B. Slemmons, and J.L. Werle. 2006. Latest Quaternary Fault Movement Along the Las Vegas Valley Fault System, Clark County, Nevada. *Environmental & Engineering Geoscience*. Vol. XII, No. 2. pp. 181-193.
- Langenheim, V.E., R.J Blakely, W.R. Page, S.C. Lundstrom, G.L. Dixon, and R.C. Jachens. 2005. *Geophysical Framework of the Las Vegas 30' x 60' Quadrangle, California*. Pamphlet accompanying the United States Geological Survey Scientific Investigation Map SIM-2814.



Las Vegas Valley Groundwater Management Program. 2011. Groundwater Level Data, Shallow System Map. November 1, 2011. http://www.lasvegsgmp.com/html/telemetry_map_shallow_sys.html.

Liu, M. 2001. Cenozoic Extension and Magmatism in the North American Cordillera: the Role of Gravitational Collapse. *Tectonophysics*. Vol. 342 (2001). pp. 407-433.

Matti, J.C., F.W. Bachhuber, D.M. Morton, and J.W. Bell. 1987. Las Vegas NW Quadrangle Geologic Map. Prepared by the Nevada Bureau of Mines and Geology Map in Collaboration with the United States Geological Survey, Scale 1:24,000.

Page, W.R., S.C. Lundstrom, A.G. Harris, V.E. Langenheim, J.B. Workman, S.A. Mahan, J.B. Paces, G.L. Dixon, P.D. Rowley, B.C. Burchfiel, J.W. Bell, and E.I. Smith. 2005. Geologic and Geophysical Maps of the Las Vegas 30' x 60' Quadrangle, Clark and Nye Counties, Nevada and Inyo County, California. United States Geological Survey Scientific Investigation Map SIM-2814 and pamphlet.





FIGURES



Aerial image ©Google Earth, 2019

FIGURE 1-1
Project Location Map
I-15 Tropicana
Las Vegas, Nevada





LIST OF MAP UNITS

QUATERNARY AND TERTIARY ROCKS
Gravelly alluvium, predominantly of alluvial fans

- Qay Young fan alluvium (Holocene and latest Pleistocene)
- Qau Undivided young and intermediate alluvium (Holocene and late Pleistocene)

Fine-grained deposits

- QTs Undivided fine-grained sediments of the Las Vegas Valley (Quaternary and Tertiary?)
- Qfy Intermittently active fluvial fine-grained alluvium (late Holocene)
- Qsy Youngest spring deposits (late Holocene)
- Qso Undivided young spring deposits (Holocene and late Pleistocene)

Basin-fill deposits

- Qm Muddy Creek Formation (Pliocene and upper Miocene)

MESOZOIC, PALEOZOIC, AND PROTEROZOIC ROCKS

- Pkt Kaibab and Toroweap Formations, undivided (Lower Permian)
- Pr Lower Permian redbeds
- PMc Calville Limestone (Permian, Pennsylvanian, and Mississippian)
Bird Spring Formation (Lower Permian to Upper Mississippian)
- Mm Monte Cristo Group (Upper and Lower Mississippian)
- MDu Mississippian and Devonian rocks, undivided (Lower Mississippian and Upper and Middle Devonian)
- Cn Nopah Formation (Upper Cambrian)
- Cbk Bonanza King Formation (Upper and Middle Cambrian)
- Xg Gneiss (Early Proterozoic)

EXPLANATION

- Contact—Dashed where approximately located. Hachure with number indicates dip direction and dip angle of contact
- Strike and dip of bedding**
- Inclined bedding
- Vertical bedding
- Overturned bedding
- Horizontal bedding
- Inclined foliation
- High-angle faults**
- High-angle normal fault—Dashed where approximately located, dotted where concealed. Ball and bar on downthrown side. Arrow and number show direction and amount of dip. Queried where inferred
- Oblique-slip and (or) strike-slip fault—Dashed where approximately located, dotted where concealed. Ball and bar on downthrown side. Arrows show relative direction of lateral offset. Queried where inferred
- Low-angle fault—Slip surface at base of gravity-slide masses and low-angle normal faults; dashed where approximately located, dotted where concealed. Hachures on upper plate. Arrow and number show direction and amount of dip. Queried where inferred
- Thrust fault—Includes reverse faults; sawteeth on upper plate; dashed where approximately located, dotted where concealed. Arrow and number show direction and amount of dip. Queried where inferred
- Geophysically inferred fault strands of the Las Vegas Valley shear zone and State Line fault zone—Ball and bar on downthrown side. Arrows show relative direction of lateral offset

North

0 0.5 1
Approximate scale in miles

FIGURE 2-1
Regional Geologic Map
I-15 Tropicana
Las Vegas, Nevada





APPENDIX A HAMMER ENERGY MEASUREMENT REPORT

Hammer Energy Measurement Report

SPT CAL

SPT HAMMER
ENERGY
MEASUREMENTS

Prepared for;
ATTN: Bob Nix

Prepared by;

SPT CAL
5512 Belem Dr.
Chino Hills, CA 91709

Cascade Drilling
4221 W Oquendo Rd
Las Vegas, NV 89118

Date: 12/27/18

909-730-2161
bc@sptcal.com

Project Title: Cascade Las Vegas 2018
P.O. Number: 12/27/18
CME 85 02-34463 Auto Hammer

Energy Transfer Ratio = 70.3 @ 41.3 blows per minute

Testing was performed on December 27, 2018 in Las Vegas, NV

Hammer Energy Measurements performed in accordance to ASTM D4633 using an approved and calibrated SPT Analyzer from Pile Dynamics, Inc.

PRESENTATION OF SPT ANALYZER TEST DATA

1. Introduction

This report presents the results of SPT Hammer Energy Measurements recorded with an SPT Analyzer from Pile Dynamics carried out on December 27, 2018 in Las Vegas, NV

2. Field Equipment and Procedures

The CME 1050 had a mounted CME Auto Hammer. The CME Auto Hammer uses a 140 lb. weight dropped 30" on to an anvil above the bore hole. AWJ drill rod connects the anvil to a split spoon type soil sampler inside an 8" o.d. hollow stem auger at the designated sample depth. After a seeding blow the sampler is driven 18". The number of blows required to penetrate the last 12" is referred to as the "N value", which is related to soil strength.


The first recording was taken at 3' below ground surface and then every 3' to final recording at 15'.

3. Instrumentation

An SPT Analyzer from Pile Dynamics was used to record and the process the data. The raw data was stored directly in the SPT Analyzer computer with subsequent analysis in the office with PDA-W and PDIPlot software. The measurements and analysis were conducted in general accordance with ASTM D4945 and ASTM D6066 test standards.

The SPT Analyzer is fully compliant with the minimum digital sampling frequency requirements of ASTM D4633-05 (50 kHz) and EN ISO 22476-3:2005 (100 kHz), as well as with the low pass filter, (cutoff frequency of 5000 Hz instead of 3000 Hz) requirements of ASTM D4633-05. All equipment and analysis also conform to ASTM D6066.

A 2' instrumented section of AWJ rod, with two sets of accelerometers and strain transducers mounted on opposite sides of the drill rod, was placed below the anvil. It measured strain and acceleration of every hammer blow. The SPT Analyzer then calculates the amount of energy transferred to the rod by force and velocity measurements.



4. Observations

The drill rig motor is diesel fueled. The drill and sample equipment looked to be well operated and maintained.

5. Results

Results from the SPT Hammer Energy Measurements are summarized below. It shows the Energy Transfer Ratio (ETR) at each sampling depth. ETR is the ratio of the measured maximum transferred energy to rated energy of the hammer which is the product of the weight of the hammer times the height of the fall. $140 \text{ lb} \times 30'' = 4200 \text{ lb-in} = 0.350 \text{ kip-ft}$.

Energy Transfer Ratio = 70.3 @ 41.3 blows per minute

$$N_{60} = (ETR/60)N$$

Depth	ETR%	BPM
3	70.1	40.8
6	69.9	41.0
9	70.5	41.3
12	70.6	41.6
15	70.2	41.8
Average	70.3	41.3

If you have any questions please do not hesitate to call or email.

Thank you,

Brian Serl
Calibration Engineer
SPT CAL
909-730-2161
bc@sptcal.com



APPENDIX B


BORING LOCATION MAPS

STATE	PROJECT NO.	COUNTY	SHEET NO.
NEVADA	SP1-015-1(75)	CLARK	1

PRELIMINARY

SUBJECT TO REVISION
09-JUL-2019

T21S R61E




LEGEND

- Approximate Boring Location
- Boring Number → BH-19-08 (120')
- Boring Depth →

BH-19-08 (120')
Elev 2052.38'

BH-19-09 (100')
Elev 2061.47'





STATE OF NEVADA
DEPARTMENT OF TRANSPORTATION

FIGURE 3 I-15 TROPICANA BORING LOCATION MAP

STATE	PROJECT NO.	COUNTY	SHEET NO.
NEVADA	SP1-015-1(75)	CLARK	2

PRELIMINARY
 SUBJECT TO REVISION
 09-JUL-2019




BH-19-10 (100')
 Elev 2139.42'

IR015 - CL XX.X
 H-2263

- LEGEND -

- Approximate Boring Location
- Boring Number → BH-19-10 (100')
- Boring Depth →



STATE OF NEVADA
 DEPARTMENT OF TRANSPORTATION

FIGURE 4

**I-15 TROPICANA
 BORING LOCATION MAP**

2 OF 2



APPENDIX C

SUBSURFACE EXPLORATION DATA

Subsurface Exploration Data

B-19-01 through B-19-10

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/04/19

END DATE: 04/08/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'56.60936" LONGITUDE W115°10'51.73387"

BORING B-19-01

PROJECT No. G-17-162

GROUND ELEV. 2063.8

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/04/19	16	2047.8
04/10/19	17.3	2046.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2060	6.0							FILL	FILL: Asphaltic Concrete, 8 inches -FILL: Aggregate Base, 7 inches -FILL: Silty SAND with gravel, slightly moist, light brown -FILL: CLSM	
	7.5								5.50 Clayey SAND with gravel, slightly moist, light brown	
2056	9.0	1 2	BULK RING	6-17-17	34	100 0	G, A, DD, M, S, Ch, R, RV	SC	-medium dense	
	10.0								-dense, light gray-brown	
2052	11.5	3	SPT	6-9-17	26	100	M			
	13.00								-partially cemented	
	15.0							CAL	CALICHE, very hard, dry, light brown	11 min/ft 8 min/ft 3 min/ft
2048	16.00	4	RING	50/0"	R	0			-moderately hard	
	18.00							SC	Clayey SAND, moist, light brown	
2044	20.0								Lean CLAY with sand, moist, light brown	
	21.5	5	SPT	3-3-4	7	100			-stiff	ppt=1.75 tsf
2040	25.0							CL	-sandy, few caliche nodules	
	26.5	6	RING	13-18-25	43	100	G, A, DS		-hard	
2036	28.50								-partially cemented	
	29.50							CAL	CALICHE, moderately hard, dry, light brown	2-3 min/ft
	30.0							SC	Clayey SAND, moist, light brown	

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/04/19

END DATE: 04/08/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'56.60936" LONGITUDE W115°10'51.73387"

BORING B-19-01

PROJECT No. G-17-162

GROUND ELEV. 2063.8

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/04/19	16	2047.8
04/10/19	17.3	2046.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2032	31.5	7	SPT	9-21-16	37	100		SC	Clayey SAND, dense, moist, light brown	
	33.50									2-3 min/ft
2028	35.0	8	RING	50/1"	R	0		CAL	CALICHE, moderately hard, dry, light brown	
	36.00									
2024	40.0							CL	Sandy lean CLAY, partially cemented, moist, light gray-brown	
									-uncemented	
	41.1	9	SPT	4-25-50/1"	R	100	M		-hard	ppt=1.0 tsf
										4 min/ft
2020	45.0								CALICHE, hard, dry, light brown	
										6 min/ft
										4 min/ft
2016	49.0	10	RING	50/0"	R	0		CAL	-very hard	16 min/ft
										13 min/ft
	50.0									11 min/ft
										13 min/ft
	51.5	11	SPT	2-2-4	6	100	M, G, A,	CL	Sandy lean CLAY, few caliche nodules, medium stiff, very moist, light olive-gray	Changed bit
2012	55.0								Clayey SAND, loose, moist, light brown	
2008	56.5	12	RING	12-39-47	86	100	UU	SC	-partially cemented, very dense	
2004	60.0									

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/04/19

END DATE: 04/08/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'56.60936" LONGITUDE W115°10'51.73387"

BORING B-19-01

PROJECT No. G-17-162

GROUND ELEV. 2063.8

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/04/19	16	2047.8
04/10/19	17.3	2046.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2000	61.5	13	SPT	9-11-8	19	100	M, G	SC	Clayey SAND, few caliche nodules, medium dense, very moist, light brown	ppt=1.0 tsf
	63.50									
1996	65.0							GC	Clayey GRAVEL with sand, very moist, light brown and gray -medium dense	
	66.5	14	RING	11-10-13	23	100	G, A			
1992	70.0							CH	Sandy fat CLAY with gravel (caliche nodules), very moist, light brown -very stiff	
	71.5	15	SPT	14-8-10	18	100				
1988	75.0									
	76.4	16	SPT	8-11-50/5"	R	100				
1984	79.00							SC	Clayey SAND with gravel, partially cemented, very dense, slightly moist, light gray -uncemented	
	80.0							CAL	79.50 CALICHE, moderately hard, dry, light gray	
1980	81.5	17	RING	19-11-11	22	100		SC	Clayey SAND, partially cemented, medium dense, slightly moist, light gray -uncemented, medium dense	ppt=0.5 tsf
	85.0							CL	Sandy lean CLAY, few caliche nodules, moist, brown -occasional partially cemented layers	
1976	86.5	18	TUBE			100	A, UU			ppt=1.5 tsf
	88.0	19	SPT	4-6-6	12	100			-stiff	ppt=0.75 tsf
	88.50									
	90.0							SC	Clayey SAND with gravel, slightly moist, light gray	

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/04/19

END DATE: 04/08/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'56.60936" LONGITUDE W115°10'51.73387"

BORING B-19-01

PROJECT No. G-17-162

GROUND ELEV. 2063.8

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/04/19	16	2047.8
04/10/19	17.3	2046.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1972	91.3	20	RING	12-23-50/ 3"	R	100		SC	Clayey SAND with gravel, very dense, slightly moist, light gray -partially cemented	ppt=1.0 tsf
	93.00								Sandy fat CLAY, moist, brown	
1968	95.0								-very stiff	
	96.5	21	SPT	6-11-6	17	100		CH		
1964	100.0									
	101.5	22	RING	6-23-38	61	100		SC	Clayey SAND with gravel, dense, moist, light brown	
									Bottom of boring at 101.5 feet	
1960										
1956										
1952										
1948										
1944										

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/03/19

END DATE: 04/04/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'59.34843" LONGITUDE W115°10'52.39264"

BORING B-19-02

PROJECT No. G-17-162

GROUND ELEV. 2066.2

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/04/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/03/19	18.5	2047.7
04/04/19	18.5	2047.7

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2064	4.0							FILL	FILL: Asphaltic Concrete, 7 inches -FILL: Aggregate Base, 7 inches -FILL: Clayey SAND with gravel, slightly moist, light brown	
	5.0							SC	Clayey SAND, trace gravel, slightly moist, light brown -loose	
2060	6.5	2	RING BULK	5-6-9	15	100 100	DD, M, G, A		Silty SAND, slightly moist, light brown	
	7.5									
	8.0							SM	-medium dense	
	9.0	3	SPT	6-7-7	14	100	Ch			
	10.0									
2056	11.5	4	RING	7-12-20	32	100	G, A, DS	SC	Clayey SAND, medium dense, slightly moist, light brown	
	12.5							CAL	CALICHE, moderately hard, dry, light brown	1-2 min/ft
2052	15.0									
	16.5	5	SPT	14-12-11	23	0		SC	Clayey SAND, slightly moist, light brown -medium dense	
	17.0									
2048	20.0							CAL	CALICHE, moderately hard, dry, light brown -very hard	12 min/ft
	21.0							SC	Clayey SAND, medium dense, moist, brown	
2044	21.5	6	RING	6-8-9	17	100	G, A, UU		Sandy lean CLAY, few caliche nodules, stiff, moist, light tan	ppt=1.0 tsf
	25.0							CL		
2040	26.5	7	SPT	4-6-12	18	100			Clayey SAND, few caliche nodules, medium dense, very moist, light gray	
	30.0							SC	-partially cemented	

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/03/19

END DATE: 04/04/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'59.34843" LONGITUDE W115°10'52.39264"

BORING B-19-02

PROJECT No. G-17-162

GROUND ELEV. 2066.2

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/04/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/03/19	18.5	2047.7
04/04/19	18.5	2047.7

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2036	30.1	8	RING	50/1"	R	0		CAL	30.50 CALICHE, hard, dry, light brown Clayey SAND, moist, light gray and brown -thin caliche lens	
2032	35.0							SC		
	36.5	9	SPT	5-6-20	26	100			-dense -partially cemented	
2028									38.00 Clayey GRAVEL with sand, moist, brown -medium dense	
	40.0							GC		
	41.5	10	RING	9-19-16	35	100	G, A, UU			
2024										
	45.0									
	48.3	11	SPT	50/3"	R	0			45.00 CALICHE, hard, dry, light brown -thin partially cemented layer	6 min/ft 4 min/ft 3 min/ft
2020								CAL		
	50.0								49.00 Silty SAND, very dense, wet, light brown	
2016	50.9	12	RING	29-50/5"	R	100	DD, M, G			
									-moist	
2012	55.0							SM		
	56.5	13	SPT	7-14-12	26	100	M, G, A		-dense	
2008										
	60.0									

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/03/19

END DATE: 04/04/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°05'59.34843" LONGITUDE W115°10'52.39264"

BORING B-19-02

PROJECT No. G-17-162

GROUND ELEV. 2066.2

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/04/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/03/19	18.5	2047.7
04/04/19	18.5	2047.7

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2004	61.3	14	RING	4-27-50/4"	R	100		SM	Silty SAND, very dense, moist, light brown -partially cemented, slightly moist, light gray	
	63.50							CAL	64.00 CALICHE, hard, dry, light gray	
2000	65.0								Sandy fat CLAY, partially cemented, slightly moist, light gray	ppt=4.5 tsf
	65.7	15	SPT	21-50/2"	R	100			-hard -uncemented, few caliche nodules, very moist, light gray and brown	
1996	70.0								-very stiff	ppt=1.0 tsf
	71.5	16	RING	4-11-12	23	100	A, UU	CH	-very moist, brown	
1992	75.0								-very stiff	ppt=0.5 tsf
	76.5	17	SPT	6-8-8	16	100				
1988	80.0									
	81.5	18	RING	7-11-12	23	100	G, A	SM	Silty SAND with gravel (caliche nodules), medium dense, very moist, light gray	
1984	82.00									
	85.0								Sandy lean CLAY, moist, brown	ppt=1.5 tsf
1980	86.0	19	TUBE			100	A, UU	CL	-stiff	
	87.5	20	SPT	6-5-6	11	100	M			
	90.0									

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/03/19

END DATE: 04/04/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

LATITUDE N36°05'59.34843" LONGITUDE W115°10'52.39264"

EQUIPMENT CME 85

BORING B-19-02

DRILLING COMPANY Cascade

PROJECT No. G-17-162

OPERATOR M. Cain

GROUND ELEV. 2066.2

ENGINEER J. Scheffner

HAMMER DROP SYSTEM Auto (ETR=70.3)

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/03/19	18.5	2047.7
04/04/19	18.5	2047.7

BACKFILLED with CLSM DATE 04/04/19

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1976	91.5	21	TUBE			100		SC	Clayey SAND, moist, light brown -with gravel, partially cemented, very dense, light gray	4 min/ft
	92.3	22	SPT	23-50/3"	R	100	M, G			
1972	95.0							CAL	CALICHE, hard, dry, light gray	
		23	RING	50/0"	R	0				
1968	100.0							SC	Clayey SAND, few caliche nodules, moist, brown -medium dense	
	101.5	24	RING	13-12-17	29	100				
1964									-small silty sand lenses Bottom of boring at 101.5 feet	

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/01/19

END DATE: 04/01/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.56404" LONGITUDE W115°10'52.85753"

BORING B-19-03

PROJECT No. G-17-162

GROUND ELEV. 2074.1

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/02/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/01/19	39	2035.1
04/02/19	33.8	2040.3

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2072								FILL	FILL: Asphaltic Concrete, 2 inches -FILL: Aggregate Base, 5 inches -FILL: Asphaltic Concrete, 9 inches -FILL: Silty SAND with gravel, slightly moist, light brown	
	5.0							CAL	3.50 4.50 CALICHE, moderately hard, dry, light gray	2 min/ft
2068	6.5	2	RING	9-14-15	29	100	DD, M, G, A	SC	Clayey SAND, slightly moist, light brown and gray mottled -medium dense	
	7.5	1	BULK			100			-medium dense -light gray	
	9.0	3	SPT	7-8-11	19	100	Ch		-light brown	
2064	10.9	4	RING	50/2"	R	0			-partially cemented, very dense -uncemented	
2060	15.0								-medium dense	
	16.5	5	SPT	5-8-14	22	100				
2056	20.0									
	21.5	6	RING	4-18-45	63	100	A, DS	-trace cementation, dense		
2052	25.0							-partially cemented, light brown-gray		
	25.9	7	SPT	25-50/5"	R	100		-very dense		
2048								-thin caliche lens		
	30.0									

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/01/19

END DATE: 04/01/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.56404" LONGITUDE W115°10'52.85753"

BORING B-19-03

PROJECT No. G-17-162

GROUND ELEV. 2074.1

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/02/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/01/19	39	2035.1
04/02/19	33.8	2040.3

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2044	31.5	8	RING	28-35-43	78	100	A, UU	CL-ML	Sandy silty CLAY, few caliche nodules, hard, moist, light brown and gray	ppt=2.5 tsf
2040	35.0									
2036	36.5	9	SPT	9-12-14	26	100		SC	Clayey SAND, dense, slightly moist, light brown -thin partially cemented layer -wet -partially cemented, very dense -uncemented -with gravel (caliche nodules), medium dense	
2032	40.0									
2028	40.9	10	RING	13-50/5"	R	100				
2024	45.0									
2024	46.5	11	SPT	12-9-6	15	100	M, G, A	GC	CALICHE, moderately hard, dry, light gray Clayey GRAVEL with sand, partially cemented, moist, light brown -uncemented -dense	
2020	47.50									
2020	50.0							GC	-medium dense	
2016	51.5	12	RING	20-27-27	54	100				
2016	55.0							CL	Sandy lean CLAY, few caliche nodules, very stiff, moist, brown	
2016	56.5	13	SPT	26-14-10	24	100				
2016	60.0									

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/01/19

END DATE: 04/01/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.56404" LONGITUDE W115°10'52.85753"

BORING B-19-03

PROJECT No. G-17-162

GROUND ELEV. 2074.1

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/02/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/01/19	39	2035.1
04/02/19	33.8	2040.3

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2012	61.5	14	RING	8-7-10	17	100	DD, M, A, C	CL	Sandy lean CLAY, few caliche nodules, stiff, moist, brown	ppt=1.25 tsf
	65.0								-stiff	ppt=1.0 tsf
2008	66.5	15	SPT	4-4-4	8	100		CL		
	70.0								-very stiff	
2004	71.5	16	RING	9-15-50	65	100	G, A, UU	SC-SM	71.00 Silty, clayey SAND with gravel, very dense, very moist, brown	
	75.0								72.50 Sandy fat CLAY, very moist, brown	
2000	75.0							CH		
	76.5	17	SPT	6-4-6	10	25			-stiff	
1996	80.0							CH		
	82.0	18	TUBE			100	A, UU		82.00	
1992	83.5	19	SPT	15-15-14	29	100		SM	Silty SAND, dense, wet, light brown	
	85.0								-very moist, brown	
1988	86.5	20	RING	6-15-21	36	100	G, A	SM	-medium dense	
	90.0								-with gravel (caliche nodules), light gray	

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/01/19

END DATE: 04/01/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.56404" LONGITUDE W115°10'52.85753"

BORING B-19-03

PROJECT No. G-17-162

GROUND ELEV. 2074.1

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/02/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/01/19	39	2035.1
04/02/19	33.8	2040.3

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS	
		NO.	TYPE	6 Inch Increments	Last foot						
1984	92.0	21	TUBE			100		SM	Silty SAND with gravel (caliche nodules), very moist, light brown -no gravel, medium dense -medium dense		
	93.5	22	SPT	6-6-7	13	100	M, G, A				
1980	95.0										
	96.0	23	TUBE			100					
	97.5	24	SPT	11-14-8	22	100					
1976	100.0										
	101.4	25	RING	13-40-50/5"	R	100		CL	100.50 101.40	Sandy lean CLAY, hard, moist, brown -partially cemented, slightly moist, light gray Bottom of boring at 101.4 feet	ppt=3.5 tsf
1972											
1968											
1964											
1960											
1956											

EXPLORATION LOG

SHEET 1 OF 5



START DATE: 03/18/19

END DATE: 03/20/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.10614" LONGITUDE W115°10'52.65259"

BORING B-19-04

PROJECT No. G-17-162

GROUND ELEV. 2071.9

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING Mud-Rotary (0-65') 3 7/8" OD

METHOD HS Auger (65-120') 8" OD

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/25/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/18/19	31	2040.9
03/25/19	30	2041.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	3.0								FILL: Asphaltic Concrete, 9 inches -FILL: Aggregate Base, 18 inches -FILL: Clayey SAND with gravel, slightly moist, light brown -FILL: Silty SAND with gravel, slightly moist, light brown	
2068	5.0	1	BULK			100				
	6.5	2	SPT	28-28-26	54	100	M, G			
2064	7.5									
	9.0	3	RING	35-35-43	78	100				
	10.0							FILL		
	11.5	4	SPT	18-35-36	71	100	M, G			
2060	15.0									
2056	15.9	5	RING	36-50/5"	R	100				
	20.0								19.50	
2052	21.5	6	SPT	8-20-27	47	100	Ch		Sandy lean CLAY, hard, few gravel, slightly moist, light brown	
	25.0							CL		
2048	26.5	7	RING	8-14-17	31	100	G, A, DS		-very stiff	
	30.0								27.00	
2044								CAL	CALICHE, moderately hard, dry, light brown and gray -hard to very hard -very hard	

EXPLORATION LOG

SHEET 2 OF 5



START DATE: 03/18/19

END DATE: 03/20/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.10614" LONGITUDE W115°10'52.65259"

BORING B-19-04

PROJECT No. G-17-162

GROUND ELEV. 2071.9

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING Mud-Rotary (0-65') 3 7/8" OD

METHOD HS Auger (65-120') 8" OD

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/25/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/18/19	31	2040.9
03/25/19	30	2041.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2040	35.0	8	SPT	50/0"	R	0		CAL	31.00 CALICHE, very hard, dry, light brown and gray	ppt=4.25 tsf 4 min/ft; 500 psi
								CL	Sandy lean CLAY, partially cemented, moist, light brown -uncemented -partially cemented, light brown and gray -light brown, hard	
2036	36.5	9	RING	29-20-17	37	100	A	36.00	Silty, clayey SAND, trace caliche nodules, medium dense, moist, light brown	
2032	40.0							SC-SM	40.00	
		10	SPT	6-5-6	11	100	M, G, A	Clayey SAND, trace caliche nodules, medium dense, very moist, light gray and olive-gray		
2028	45.0								-very thin caliche lens	
		11	TUBE			0		SC	-partially cemented, slightly moist -uncemented, dense, light brown -thin partially cemented layer	
2024	48.5	12	SPT	32-20-13	33	100				
									-very dense, with gravel (caliche nodules)	
2020	51.5	13	RING	13-37-35	72	100			53.50	
								CAL	55.00 CALICHE, hard, dry, light brown -moderately hard	
2016	56.5	14	SPT	23-12-18	30	100	M, G	SC	56.50 Clayey SAND, dense, moist, brown	
								CL	Sandy lean CLAY, trace caliche nodules, moist, brown	
2012	60.0									

EXPLORATION LOG

SHEET 3 OF 5



START DATE: 03/18/19

END DATE: 03/20/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.10614" LONGITUDE W115°10'52.65259"

BORING B-19-04

PROJECT No. G-17-162

GROUND ELEV. 2071.9

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING Mud-Rotary (0-65') 3 7/8" OD

METHOD HS Auger (65-120') 8" OD

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/25/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/18/19	31	2040.9
03/25/19	30	2041.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2008	61.5	15	RING	4-9-19	28	100	A, UU	CL	Sandy lean CLAY, trace caliche nodules, very stiff, moist, brown	ppt=2.0 tsf
	65.0								-thin partially cemented layer -very stiff	ppt=1.25 tsf
2004	66.5	16	SPT	11-10-9	19	100		CL		
	70.0									
2000	71.5	17	RING	5-15-35	50	100	G, A	CL-ML		ppt=1.75 tsf
	75.0								Sandy silty CLAY, trace caliche nodules, hard, moist, brown -partially cemented	
1996	75.0	18	SPT	50/1"	R	0		CAL		
	77.0								CALICHE, hard to very hard, dry, light gray brown	
1992	80.0							SC	Clayey SAND, few caliche nodules, dense, very moist, brown	Caliche nodule in shoe
	81.5	19	RING	28-31-26	57	0			-thin silty sand layer -partially cemented	
1988	85.0							CL		
	86.5	20	SPT	23-8-9	17	100			Sandy lean CLAY, few caliche nodules, very stiff, moist, brown	
1984	86.5							CL		
	90.0									

EXPLORATION LOG

SHEET 4 OF 5



START DATE: 03/18/19

END DATE: 03/20/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.10614" LONGITUDE W115°10'52.65259"

BORING B-19-04

PROJECT No. G-17-162

GROUND ELEV. 2071.9

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING Mud-Rotary (0-65') 3 7/8" OD

METHOD HS Auger (65-120') 8" OD

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/25/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/18/19	31	2040.9
03/25/19	30	2041.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1980	91.5	21	RING	8-8-9	17	100	A, UU	CL	Sandy lean CLAY, few caliche nodules, stiff, very moist, brown	ppt=0.75 tsf
	95.0									
1976	96.5	22	SPT	5-2-2	4	100	M, A	CL	-medium stiff, wet	ppt=0.0 tsf
	100.0									
1972	101.5	23	RING	9-7-7	14	100	DD, M	CL	-stiff	ppt=1.0 tsf
	105.0									
1968	107.0	24	TUBE			100		SC	Clayey SAND with gravel, medium dense, very moist, light brown	
	108.5	25	SPT	10-31-25	56	100		SM	Silty SAND, very dense, wet, light brown	
1964	110.0							SC	Clayey SAND, few caliche nodules, very dense, very moist, light brown -thin partially cemented layer	
	111.5	26	RING	6-7-8	15	100	DD, M, G	SM	Silty SAND, medium dense, wet, light brown	
1960	113.0							SC	Clayey SAND, medium dense, very moist, light brown	
	115.0							CL	Sandy lean CLAY, caliche nodules, stiff, moist, light brown	ppt=0.0 tsf
116.5	27	SPT	3-2-5	7	100	M, A				
1952	120.0									

EXPLORATION LOG

SHEET 5 OF 5



START DATE: 03/18/19

END DATE: 03/20/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.10614" LONGITUDE W115°10'52.65259"

BORING B-19-04

PROJECT No. G-17-162

GROUND ELEV. 2071.9

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING Mud-Rotary (0-65') 3 7/8" OD

METHOD HS Auger (65-120') 8" OD

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/25/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/18/19	31	2040.9
03/25/19	30	2041.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	121.5	28	RING	14-14-19	33	100		SM	Silty SAND, medium dense, wet, light brown	
									Bottom of boring at 121.5 feet	
1948										
1944										
1940										
1936										
1932										
1928										
1924										

EXPLORATION LOG

SHEET 1 OF 5



START DATE: 03/27/19

END DATE: 03/29/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'01.02693" LONGITUDE W115°10'50.30150"

BORING B-19-05

PROJECT No. G-17-162

GROUND ELEV. 2055.3

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/27/19	23	2032.3
03/29/19	19.8	2035.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2052	4.0							FILL	FILL: Asphaltic Concrete, 2 inches -FILL: Concrete, 12 inches -FILL: Aggregate Base, 10 inches -FILL: Clayey SAND with gravel, slightly moist, light brown	
	5.0								Lean CLAY with sand, gypsum, slightly moist, light brown -very stiff	
2048	6.5	2	RING BULK	6-8-15	23	50 100	G, DS A, RV	CL	-light gray	
	7.5									
	8.0									
	9.0	3	SPT	18-15-35	50	100			-partially cemented, hard	
	10.0									
2044	10.0	4	RING	50/1"	R	0		CAL	CALICHE, very hard, dry, light brown	8 min/ft
	11.0									
	15.0							CL	Sandy lean CLAY, moist, light gray -very moist	
2040	15.5								-medium stiff	ppt=0.25 tsf
	16.5	5	SPT	3-4-3	7	100	M, A	SM	Silty SAND, loose, wet, light brown	
	20.0							CL	Sandy lean CLAY, medium stiff, moist, light gray	
2036	20.9	6	RING	5-50/5"	R	0			-partially cemented, hard	
	22.0									
	23.0							CAL	CALICHE, hard, dry, light gray	5 min/ft
2032	25.0								Sandy lean CLAY, occasional sand lenses, moist, light brown and gray -stiff	ppt=1.5 tsf
	26.5	7	SPT	7-4-5	9	100	A, Ch	CL		
2028	30.0									

EXPLORATION LOG

SHEET 2 OF 5



START DATE: 03/27/19

END DATE: 03/29/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'01.02693" LONGITUDE W115°10'50.30150"

BORING B-19-05

PROJECT No. G-17-162

GROUND ELEV. 2055.3

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/27/19	23	2032.3
03/29/19	19.8	2035.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	30.3	8	RING	50/4"	R	0		CL	30.50 Sandy lean CLAY, partially cemented, hard, moist, light brown	2 min/ft
2024								CAL	32.00 CALICHE, moderately hard to hard, dry, light brown	
	35.0							SC	Clayey SAND, partially cemented, moist, light brown -uncemented, few caliche nodules -very dense	
2020	36.5	9	SPT	18-19-26	45	100	M, G, A			
	40.0							CAL	39.00 -partially cemented CALICHE, hard, dry, light brown	6 min/ft
2016		10	RING	50/0"	R	0				
	45.0							SC	44.50 -moderately hard Clayey SAND, medium dense, moist, light brown	9 min/ft
2012	46.5	11	SPT	10-13-7	20	100				
	50.0							CL	46.00 -medium dense Sandy lean CLAY, very stiff, moist, light brown	11 min/ft
2008										
	51.5	12	RING	6-8-22	30	100	DD, M, G	SM	50.00 Silty SAND, medium dense, moist, light brown	ppt=1.0 tsf
2004										
	55.0							SM	-few caliche nodules -dense	
2000	56.5	13	SPT	6-13-15	28	100	M, A			
	60.0								-thin partially cemented layer	
1996										

EXPLORATION LOG

SHEET 3 OF 5



START DATE: 03/27/19

END DATE: 03/29/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

LATITUDE N36°06'01.02693" LONGITUDE W115°10'50.30150"

EQUIPMENT CME 85

BORING B-19-05

DRILLING COMPANY Cascade

PROJECT No. G-17-162

OPERATOR M. Cain

GROUND ELEV. 2055.3

ENGINEER J. Scheffner

HAMMER DROP SYSTEM Auto (ETR=70.3)

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/27/19	23	2032.3
03/29/19	19.8	2035.5

BACKFILLED with CLSM DATE 03/29/19

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	61.5	14	RING	6-9-11	20	100	A, UU	SM 60.50	Sandy fat CLAY, stiff, moist, brown	ppt=1.25 tsf
1992	65.0							CH 65.00		
	67.0	15	TUBE			100		SC	Clayey SAND with gravel (caliche nodules), moist, brown -medium dense	
1988	68.5	16	SPT	10-8-10	18	100	M, G			
	70.0									
1984	71.5	17	RING	16-13-15	28	100	A, UU		Gravelly lean CLAY with sand, moist, brown -very stiff	ppt=1.75 tsf
	75.0							CL		
1980	76.5	18	SPT	7-3-8	11	100			-stiff	
	80.0									
1976	81.5	19	RING	4-7-9	16	100			Sandy fat CLAY, trace caliche nodules, stiff, moist, brown	ppt=1.25 tsf
1972	85.0							CH		
	85.4	20	SPT	50/5"	R	100				
									Clayey SAND, slightly cemented, very dense, slightly moist, light gray	
1968	90.0							SC 89.00		
								CL	Sandy lean CLAY, trace caliche nodules, moist,	ppt=1.0 tsf

EXPLORATION LOG

SHEET 4 OF 5



START DATE: 03/27/19

END DATE: 03/29/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'01.02693" LONGITUDE W115°10'50.30150"

BORING B-19-05

PROJECT No. G-17-162

GROUND ELEV. 2055.3

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/27/19	23	2032.3
03/29/19	19.8	2035.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1964	92.0	21	TUBE			100	A, U	CL	brown Sandy lean CLAY, trace caliche nodules, moist, brown	Sample recovered using SPT sampler
	93.5	22	SPT	4-8-9	17	100			-very stiff	
	95.0									
1960	96.5	23	RING	6-10-15	25	100	DD, M		-very stiff, with gravel (caliche nodules), very moist, light brown	
	100.0									
	101.5	24	SPT	5-5-9	14	100	M, G, A		-stiff, more caliche nodules, light gray -light gray and brown	
	105.0									
1952	106.5	25	RING	9-7-9	16	0			-stiff, fewer caliche nodules, mottled with dark brown	
	107.0									
1948	110.0								CH	
	111.5	26	TUBE			100				
1944	113.0	27	SPT	7-4-41	45	100	M, G	SM	Silty SAND, very dense, wet, light brown	
	115.0									
1940	116.5	28	RING	7-10-16	26	50		CH	Sandy fat CLAY, few caliche nodules, very stiff, moist, brown	ppt=0.75 tsf
	120.0									

EXPLORATION LOG

SHEET 5 OF 5



START DATE: 03/27/19

END DATE: 03/29/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'01.02693" LONGITUDE W115°10'50.30150"

BORING B-19-05

PROJECT No. G-17-162

GROUND ELEV. 2055.3

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/27/19	23	2032.3
03/29/19	19.8	2035.5

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	121.5	29	SPT	5-8-14	22	100		CH	Sandy fat CLAY, few caliche nodules, very stiff, moist, brown	ppt=1.75 tsf
	121.50								Bottom of boring at 121.5 feet	
1932										
1928										
1924										
1920										
1916										
1912										
1908										

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/15/19

END DATE: 04/16/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'03.17881" LONGITUDE W115°10'47.41719"

BORING B-19-06

PROJECT No. G-17-162

GROUND ELEV. 2070.7

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/15/19	34	2036.7
04/19/19	32.9	2037.8

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2068	5.0							FILL	FILL: Asphaltic Concrete, 7 inches -FILL: Aggregate Base, 10 inches -FILL: Silty GRAVEL with sand, slightly moist, light brown -FILL: Silty SAND, trace gravel, slightly moist, light brown -with gravel	
2064	6.5	2	RING	6-9-9	18	100	DD, M, G, A			
	7.5	1	BULK			100				
	9.0	3	SPT	10-10-6	16	100	Ch			
2060	10.0									
	11.5	4	RING	6-7-10	17	100	G, DS			
2056	15.0									
	16.5	5	SPT	4-7-11	18	100				
2052	20.0									
	21.5	6	RING	18-24-35	59	100	DD, M, G, A			
2048	25.0						SM			
2044	26.5	7	SPT	4-4-9	13	100		SC	Clayey SAND, few gravel, medium dense, slightly moist, light brown -clay lenses	
	30.0									

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/15/19

END DATE: 04/16/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'03.17881" LONGITUDE W115°10'47.41719"

BORING B-19-06

PROJECT No. G-17-162

GROUND ELEV. 2070.7

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/15/19	34	2036.7
04/19/19	32.9	2037.8

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS	
		NO.	TYPE	6 Inch Increments	Last foot						
2040	30.9	8	RING	19-50/5"	R	100		SC	30.50	6 min/ft	
								GP-GM	31.00		Poorly graded GRAVEL with silt and sand, very dense, slightly moist, light brown
								CAL	34.00		CALICHE, hard, dry, light brown -moderately hard
2036	35.0	9	SPT	4-8-9	17	100		SC	40.00	1-2 min/ft	
											Clayey SAND, silty sand lenses, medium dense, wet, light gray -medium dense
2032	40.0	10	RING	4-4-8	12	100	G, A	SM	41.50	1 min/ft	
								GM	42.50		Silty GRAVEL with sand, wet, light brown
								SM	45.00		Silty SAND, medium dense, wet, light brown
2028	45.0	11	SPT	6-6-12	18	100		SC	48.00	1 min/ft	
								CAL	49.00		CALICHE, moderately hard, dry, light gray
								SC	50.00		Clayey SAND, partially cemented, slightly moist, light gray
2024	46.5	12	RING	50/1"	R	0		CAL	50.50	1 min/ft	
											CALICHE, moderately hard, dry, light gray
											Clayey SAND, moist, light brown
2020	50.0	13	SPT	8-12-11	23	100	M, G, A	SC	55.00	1 min/ft	
											-medium dense, with gravel
2016	55.0	13	SPT	8-12-11	23	100	M, G, A	SC	56.50	1 min/ft	
											-partially cemented
2012	60.0							CAL	59.50	1 min/ft	
											CALICHE, very hard, dry, light brown

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/15/19

END DATE: 04/16/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'03.17881" LONGITUDE W115°10'47.41719"

BORING B-19-06

PROJECT No. G-17-162

GROUND ELEV. 2070.7

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/15/19	34	2036.7
04/19/19	32.9	2037.8

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2008	65.0	14	RING	50/0"	R	0		CAL	CALICHE, very hard, dry, light brown	12 min/ft 26 min/ft 21 min/ft 22 min/ft 18 min/ft
2004	70.0	15	SPT	50/0"	R	0			Sandy lean CLAY, hard, moist, light brown	
2000	71.5	16	RING	11-12-12	24	0		CL	-very stiff	
1996	75.0									
	76.5	17	SPT	7-5-7	12	100	G, A		-stiff	
1992	80.0								-partially cemented, light gray-brown	
	80.3	18	RING	50/4"	R	0		CAL	CALICHE, hard, light gray-brown	6 min/ft
1988	85.0							CH	Sandy fat CLAY, moist, brown	
	86.5	19	SPT	8-19-50/5"	R	100			-hard	ppt=0.5 tsf
1984	89.0							SC	Clayey SAND, partially cemented, very dense, slightly moist, light tan -uncemented -partially cemented	
	90.0							CL	Sandy lean CLAY, trace caliche nodules, very	

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/15/19

END DATE: 04/16/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'03.17881" LONGITUDE W115°10'47.41719"

BORING B-19-06

PROJECT No. G-17-162

GROUND ELEV. 2070.7

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/15/19	34	2036.7
04/19/19	32.9	2037.8

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1980	92.0	20	TUBE			100	A, UU	CL	moist, brown Sandy lean CLAY, trace caliche nodules, very moist, brown	ppt=0.5 tsf
	93.5	21	SPT	6-50/5"	R	100			-partially cemented, hard	
1976	95.0								-uncemented, very stiff	ppt=0.75 tsf
	96.5	22	RING	7-7-15	22	100			-intermittent gravelly layers	
	100.0								-very stiff	
1972	101.5	23	SPT	11-7-8	15	100		101.50	Bottom of boring at 101.5 feet	
1968										
1964										
1960										
1956										
1952										

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/17/19

END DATE: 04/18/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.23381" LONGITUDE W115°10'48.36073"

BORING B-19-07

PROJECT No. G-17-162

GROUND ELEV. 2061.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/17/19	29	2032.4
04/19/19	26.3	2035.1

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2060	5.0							FILL	FILL: Asphaltic Concrete, 6 inches -FILL: Aggregate Base, 10 inches -FILL: Silty GRAVEL with sand, slightly moist, light brown	
2056	6.5	2	SPT	7-12-17	29	100	G			
	7.0	1	BULK			100				
	7.5								7.00	
2052	9.0	3	RING	7-9-12	21	100			Silty, clayey SAND, gypsum, slightly moist, light brown -medium dense	
	10.0								-medium dense	
	11.5	4	SPT	7-9-8	17	100	M, G, A			
2048	15.0							SC-SM		
	16.5	5	RING	12-23-40	63	100	Ch		-more gypsum, dense	
2044	20.0									
	20.3	6	SPT	50/3"	R	0			20.00 -partially cemented	
2040								CAL	CALICHE, hard, dry, light brown -moderately hard	8 min/ft 2 min/ft
									22.50	
								SC	Clayey SAND, slightly moist, light brown -partially cemented	
	25.0							CAL	24.00 CALICHE, moderately hard, dry, light brown	
2036	26.5	7	RING	9-10-48	58	100	DD, M	SC	24.50 CALICHE, moderately hard, dry, light brown Clayey SAND, dense, slightly moist, light brown -partially cemented, light gray	
									27.00	
								CAL	27.50 CALICHE, hard, dry, light gray	
2032	30.0							SC	Clayey SAND, partially cemented, moist, light brown -uncemented, silty sand lenses, wet	

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/17/19

END DATE: 04/18/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.23381" LONGITUDE W115°10'48.36073"

BORING B-19-07

PROJECT No. G-17-162

GROUND ELEV. 2061.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/17/19	29	2032.4
04/19/19	26.3	2035.1

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2028	31.5	8	SPT	4-3-5	8	75		SC	Clayey SAND, silty sand lenses, loose, wet, light brown	7 min/ft
								CAL	32.00 CALICHE, moderately hard, dry, light brown	
	35.0								Clayey SAND with gravel, moist, light gray-brown -partially cemented -uncemented, medium dense	
2024	36.5	9	RING	5-18-10	28	100	DD, M, G, A	SC		
									39.00	
2020	40.0								CALICHE, hard, dry, light brown	
		10	SPT	50/0"	R	0		CAL	41.00 -hard -moderately hard	
2016	45.0								Clayey SAND with gravel (caliche nodules), moist, brown	
	46.5	11	RING	5-5-6	11	100	DD, M, G, A, C	SC	-loose	
2012	50.0								49.00	
								CAL	49.50 CALICHE, moderately hard, dry, light gray	
2008	50.2	12	SPT	50/2"	R	0		SC	51.00 Clayey SAND, partially cemented, very dense, slightly moist, light gray	
								CAL	52.00 CALICHE, moderately hard, dry, light gray	
2004	55.0								54.00 Clayey SAND, moist, light gray-brown	
		13	RING	50/0"	R	0		CAL	55.50 CALICHE, hard, dry, light gray	
	60.0							CL	Sandy lean CLAY, few caliche nodules, moist, brown	

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/17/19

END DATE: 04/18/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.23381" LONGITUDE W115°10'48.36073"

BORING B-19-07

PROJECT No. G-17-162

GROUND ELEV. 2061.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/17/19	29	2032.4
04/19/19	26.3	2035.1

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2000	61.5	14	SPT	11-8-8	16	100	M, A	CL	Sandy lean CLAY, few caliche nodules, very stiff, moist, brown	ppt=1.5 tsf
	65.0									
1996	66.5	15	RING	17-9-20	29	100	M, G, A	SM	Silty SAND with gravel, medium dense, wet, light brown -clay lens	
								ML	Sandy SILT, very stiff, wet, light brown	
1992	70.0							SC	Clayey SAND, partially cemented, medium dense, moist, light brown	
	71.5	16	SPT	22-14-6	20	100			-uncemented	
1988	75.0							CH	Sandy fat CLAY, very stiff, moist, brown -with gravel (caliche nodules)	
	76.5	17	RING	8-7-11	18	100	G	SM	Silty SAND, medium dense, wet, light brown	
1984	80.0							SC	Clayey SAND with gravel (caliche nodules), medium dense, moist, light brown and gray -partially cemented	
	80.8	18	TUBE			100	A, UU	CL	Sandy lean CLAY with gravel (caliche nodules), very moist, brown	ppt=0.5 tsf
1980	82.3	19	SPT	7-8-27	35	100	G		-hard	
								SC	Clayey SAND with gravel, partially cemented, dense, slightly moist, light brown -uncemented	
1976	86.5	20	RING	15-22-13	35	100	G	CL	Sandy lean CLAY with gravel, very stiff, moist, light gray	
								SC	Clayey SAND with gravel (caliche nodules), very moist, brown	
1972	90.0									

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/17/19

END DATE: 04/18/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'06.23381" LONGITUDE W115°10'48.36073"

BORING B-19-07

PROJECT No. G-17-162

GROUND ELEV. 2061.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/17/19	29	2032.4
04/19/19	26.3	2035.1

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
	91.5	21	SPT	5-3-4	7	100		SC	91.00 Clayey SAND with gravel (caliche nodules), loose, very moist, brown	ppt=0.5 tsf
1968	95.0							CL	Sandy lean CLAY, trace caliche nodules, medium stiff, very moist, brown	
	97.0	22	TUBE			100	A			
1964	98.5	23	SPT	7-7-10	17	100			98.00 -very stiff	
	100.2							SC	100.00 Clayey SAND with gravel (caliche nodules), very dense, very moist, light gray -partially cemented	
	100.2	24	RING	50/2"	R	0			100.20 Bottom of boring at 100.2 feet	
1960										
1956										
1952										
1948										
1944										

EXPLORATION LOG

SHEET 1 OF 5



START DATE: 04/09/19

END DATE: 04/10/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'00.85298" LONGITUDE W115°10'44.98826"

BORING B-19-08

PROJECT No. G-17-162

GROUND ELEV. 2052.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/09/19	15	2037.4
04/10/19	16	2036.4

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS	
		NO.	TYPE	6 Inch Increments	Last foot						
2052								FILL	0.90	FILL: Asphaltic Concrete, 2.5 inches -FILL: Aggregate Base, 8 inches	
								SC	2.50	Clayey SAND with gravel (caliche nodules), trace gypsum, medium dense, slightly moist, light brown	
								CAL	3.00	CALICHE, hard, dry, light brown	
2048	5.0									Clayey SAND with gravel (caliche nodules), dense, slightly moist, light brown -partially cemented -uncemented, medium dense	
	6.5	2	SPT	10-6-9	15	100					
	7.5	1	BULK			100	M, G				
2044	9.0	3	RING	21-15-11	26	100	DS	SC		-medium dense	
	10.0									-trace gravel, moist, light gray	
	11.3	4	SPT	4-12-50/3"	R	100	Ch			-partially cemented, very dense	
2040	15.0							CAL	12.00	CALICHE, hard, dry, light gray-brown	4 min/ft 5 min/ft 6 min/ft
	15.0	5	RING	50/0"	R	0			15.00	Clayey SAND, very dense, moist, light gray	
2036	20.0										
2032	20.8	6	SPT	22-50/3"	R	100		SC		-partially cemented, very dense, slightly moist	
	25.0									-uncemented, very moist, light brown -loose	
2028	26.5	7	RING	4-5-8	13	100	G, A	SM	26.00	Silty SAND, loose, very moist, light brown	
									27.00	CALICHE, moderately hard, dry, light brown	1-2 min/ft
2024	30.0							CAL		-very hard	10 min/ft

EXPLORATION LOG

SHEET 2 OF 5



START DATE: 04/09/19

END DATE: 04/10/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'00.85298" LONGITUDE W115°10'44.98826"

BORING B-19-08

PROJECT No. G-17-162

GROUND ELEV. 2052.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/09/19	15	2037.4
04/10/19	16	2036.4

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2020	30.50	8	SPT	50/0"	R	0		CAL	30.50 CALICHE, very hard, dry, light brown Clayey SAND, few caliche nodules, moist, light brown -thin partially cemented layer	1-2 min/ft 9 min/ft 20 min/ft 25 min/ft ppt=1.5 tsf
	35.0							SC	-loose	
2016	36.5	9	RING	5-5-6	11	100	G, A, UU	36.50		
2012	40.0								CALICHE, moderately hard, dry, light brown	
	40.0	10	SPT	50/1"	R	0		CAL	-very hard	
2008	45.0								Silty SAND with gravel, very dense, moist, light brown	
	45.8	11	RING	32-50/4"	R	100		SM	-dense	
2004	50.0								Clayey SAND, medium dense, moist, brown	
	51.5	12	SPT	38-11-14	25	100	G	51.00		
2000	55.0								Sandy lean CLAY, moist, brown	
	55.0							CL	-stiff	
1996	56.4	13	RING	5-10-50/5"	R	100	A, UU	56.00		
	60.0							SM	Silty SAND, very dense, moist, light brown	

EXPLORATION LOG

SHEET 3 OF 5



START DATE: 04/09/19

END DATE: 04/10/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'00.85298" LONGITUDE W115°10'44.98826"

BORING B-19-08

PROJECT No. G-17-162

GROUND ELEV. 2052.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/09/19	15	2037.4
04/10/19	16	2036.4

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS	
		NO.	TYPE	6 Inch Increments	Last foot						
1992	61.5	14	SPT	28-26-19	45	100		SM	60.50		
								SC	61.50		Clayey SAND, few caliche nodules, very dense, moist, light tan
								CAL	62.00		CALICHE, moderately hard, dry, light brown Clayey SAND, moist, light gray
1988	65.0							SC		-very dense -partially cemented -uncemented	
											65.9
1984	70.0									-partially cemented -very dense	
											70.9
1980	75.0									-uncemented	
											73.00
1976	76.5									Sandy lean CLAY, few caliche nodules, moist, brown -very stiff	
											76.5
1972	80.0									-with gravel (caliche nodules) -partially cemented, hard -uncemented	
											80.0
1968	85.0									-thin partially cemented layer -thin partially cemented layer	
											86.5
1964	90.0									-hard -thin partially cemented layer -thin partially cemented layer	
											90.0

EXPLORATION LOG

SHEET 4 OF 5



START DATE: 04/09/19

END DATE: 04/10/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'00.85298" LONGITUDE W115°10'44.98826"

BORING B-19-08

PROJECT No. G-17-162

GROUND ELEV. 2052.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/10/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/09/19	15	2037.4
04/10/19	16	2036.4

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1960	91.5	20	SPT	5-4-9	13	100		CL	Sandy lean CLAY, few caliche nodules, very stiff, moist, light gray and brown	ppt=0.75 tsf
	95.0								-brown	ppt=1.0 tsf
1956	97.0	21	TUBE			100	UU			
	98.5	22	SPT	9-13-19	32	100		SM	Silty SAND, dense, very moist, light brown	
	100.0									
1952	101.5	23	RING	5-5-8	13	100		CH	Sandy fat CLAY with gravel (caliche nodules), moist, brown -stiff	ppt=1.0 tsf
	105.0									
1948	106.5	24	SPT	10-5-7	12	100	G		Clayey SAND, partially cemented, moist, brown -uncemented, few caliche nodules, medium dense	
	110.0								-more caliche nodules	
1944	111.5	25	RING	15-8-13	21	100			-trace caliche nodules, very moist, light gray, medium dense	
	115.0							SC	-fat clay lens	
1940	116.5	26	SPT	5-3-7	10	100				
	120.0								-medium dense	

EXPLORATION LOG

SHEET 5 OF 5



START DATE: 04/09/19

END DATE: 04/10/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

LATITUDE N36°06'00.85298" LONGITUDE W115°10'44.98826"

EQUIPMENT CME 85

BORING B-19-08

DRILLING COMPANY Cascade

PROJECT No. G-17-162

OPERATOR M. Cain

GROUND ELEV. 2052.4

ENGINEER J. Scheffner

HAMMER DROP SYSTEM Auto (ETR=70.3)

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/09/19	15	2037.4
04/10/19	16	2036.4

BACKFILLED with CLSM DATE 04/10/19

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1932	120.3	27	RING	50/3"	R	0		SC	120.30 -partially cemented, very dense Bottom of boring at 120.3 feet	
1928										
1924										
1920										
1916										
1912										
1908										
1904										

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 04/11/19

END DATE: 04/11/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.72498" LONGITUDE W115°10'43.92813"

BORING B-19-09

PROJECT No. G-17-162

GROUND ELEV. 2061.5

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/11/19	27	2034.5
04/19/19	26.3	2035.2

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS		
		NO.	TYPE	6 Inch Increments	Last foot							
2060	4.0							FILL	FILL: Asphaltic Concrete, 7 inches -FILL: Aggregate Base, 12 inches -FILL: Silty SAND with gravel, slightly moist, light brown -FILL: Clayey SAND, trace gravel, slightly moist, light brown			
	5.0											
2056	6.5	2 1	SPT BULK	9-5-7	12	100 100	G, A, Ch, R, RV					
	7.5											
	8.0											
	9.0	3	RING	5-16-16	32	100	DD, M					
2052	10.0											
	11.5	4	SPT	4-6-6	12	100						
2048	13.00									CL	Lean CLAY with sand, few caliche nodules, slightly moist, light brown and gray -stiff	
	15.0											
	16.5	5	RING	5-7-12	19	100	G, DS					
2044												
	20.0											
2040	21.5	6	SPT	2-6-8	14	100	M, A	CL-ML	Sandy silty CLAY, very stiff, slightly moist, light brown and gray -partially cemented, light gray			
	23.00											
	24.00						CAL					2 min/ft
	25.00						SC					Clayey SAND, partially cemented, slightly moist, light gray
2036	25.4	7	RING	50/5"	R	0		CAL	CALICHE, hard, dry, light brown -moderately hard			4 min/ft
										1 min/ft		
								SM	Silty SAND, clay lenses, wet, light brown			
2032	30.0											

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 04/11/19

END DATE: 04/11/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.72498" LONGITUDE W115°10'43.92813"

BORING B-19-09

PROJECT No. G-17-162

GROUND ELEV. 2061.5

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/11/19	27	2034.5
04/19/19	26.3	2035.2

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2028	31.5	8	SPT	9-5-6	11	100	G, A	SM	Silty SAND, clay lenses, medium dense, wet, light brown	5 min/ft
									33.00	
	35.0							CAL	CALICHE, hard, dry, light gray -moderately hard	
2024	35.8	9	RING	34-50/3"	R	0		SC	Clayey SAND, partially cemented, very dense, slightly moist, light gray	5 min/ft 3 min/ft
									36.00	
	40.0							CAL	CALICHE, hard, dry, light gray - 6-inch uncemented layer	
2020		10	SPT	50/0"	R	0				
									40.50	
	45.0							CL	Sandy lean CLAY, trace caliche nodules, moist, light brown	
2016	46.5	11	RING	6-7-16	23	100	A, UU		-very stiff -more caliche nodules	
									46.50	
	50.0							SC	Clayey SAND with gravel (caliche nodules), moist, light brown	
2012	51.5	12	SPT	3-5-9	14	100	G, A		-trace gravel, medium dense, very moist	
									52.50	
	55.0							CAL	CALICHE, very hard, dry, light brown -hard	
2008	56.5	13	RING	23-26-31	57	100			Silty SAND, some cementation, dense, moist, light gray and brown	8 min/ft 5 min/ft
									54.50	
	60.0							SM		

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 04/11/19

END DATE: 04/11/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.72498" LONGITUDE W115°10'43.92813"

BORING B-19-09

PROJECT No. G-17-162

GROUND ELEV. 2061.5

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/11/19	27	2034.5
04/19/19	26.3	2035.2

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2000	60.9	14	SPT	31-50/5"	R	100		SM	Silty SAND with gravel, very dense, wet, light brown	ppt=0.5 tsf
									62.00	
1996	65.0							CH	Sandy fat CLAY, moist, brown	
	66.5	15	RING	4-6-9	15	50	DD, M, UU		-few caliche nodules -stiff	
1992	70.0								70.00	
	71.4	16	SPT	23-50-50/5"	R	100	G	SM	Silty SAND, very dense, wet, light brown -partially cemented, light gray and brown	
1988	75.0								-uncemented -partially cemented	
	76.5	17	RING	23-49-35	84	100			-uncemented, very dense	
1984	80.0								80.50 -very dense	
	80.9	18	SPT	41-50/5"	R	100		SC	Clayey SAND, partially cemented, very dense, slightly moist, light brown-gray	
1980								CAL	83.00 CALICHE, hard, dry, light brown	
	85.0								Clayey SAND, few caliche nodules, moist, light brown	
1976	85.8	19	RING	15-50/3"	R	0		SC	-very dense -thin partially cemented layer, silty sand lenses	
									88.00	
1972	90.0							CH	Sandy fat CLAY, trace caliche nodules, moist, brown	

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 04/11/19

END DATE: 04/11/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'02.72498" LONGITUDE W115°10'43.92813"

BORING B-19-09

PROJECT No. G-17-162

GROUND ELEV. 2061.5

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 04/19/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
04/11/19	27	2034.5
04/19/19	26.3	2035.2

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1968	91.5	20	SPT	4-10-12	22	100		CH	Sandy fat CLAY, trace caliche nodules, very stiff, moist, brown	ppt=0.75 tsf
	95.9	21	RING	50/2"	R	0		SC	Clayey SAND, partially cemented, very dense, moist, light brown -uncemented -thin partially cemented layer	
1960	101.4	22	SPT	15-24-50/5"	R	100			-very dense -partially cemented	
									Bottom of boring at 101.4 feet	

EXPLORATION LOG

SHEET 1 OF 4



START DATE: 03/22/19

END DATE: 03/25/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'28.38353" LONGITUDE W115°10'50.20417"

BORING B-19-10

PROJECT No. G-17-162

GROUND ELEV. 2039.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/22/19	21	2018.4
03/25/19	19.5	2019.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2036	5.0							FILL	FILL: Asphaltic Concrete, 2 inches -FILL: Concrete, 12 inches -FILL: Aggregate Base, 10 inches -FILL: Silty GRAVEL with sand, slightly moist, light brown	
	7.0	1	BULK			100	M, G, A, Ch, RV	CL	Sandy lean CLAY, gypsum, slightly moist, light brown	
2032	7.5								-very stiff	
	8.0	2	SPT	8-9-8	17	100	G, A			
	8.5	3	RING	5-9-15	24	100	DS			
	9.0									
	10.0							CL-ML	Sandy silty CLAY, slightly moist, light brown	
2028	11.4	4	SPT	12-22-50/5"	R	100			-hard	
								CAL	CALICHE, hard, dry, light brown	4 min/ft
	15.0								Gravelly lean CLAY with sand, slightly moist, light gray-brown	
2024	16.5	5	RING	13-18-18	36	100	UU	CL	-very stiff	ppt=1.25 tsf
									-partially cemented	
2020	20.0							CAL	CALICHE, hard, dry, light brown	5 min/ft 7 min/ft 3 min/ft
		6	SPT	50/0"	R	0				
2016	25.0								Silty SAND, clayey sand layers, very moist, light gray	
	26.5	7	RING	3-3-4	7	0		SM	-loose	
2012	30.0									

EXPLORATION LOG

SHEET 2 OF 4



START DATE: 03/22/19

END DATE: 03/25/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'28.38353" LONGITUDE W115°10'50.20417"

BORING B-19-10

PROJECT No. G-17-162

GROUND ELEV. 2039.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/22/19	21	2018.4
03/25/19	19.5	2019.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
2008	31.5	8	SPT	2-2-3	5	100	G, A	SC	Clayey SAND, very moist, loose, light gray	2-3 min/ft
2004	35.0	9	RING	50/0"	R	0		CAL	CALICHE, moderately hard, dry, light gray	2-3 min/ft
2000	40.0								Clayey SAND, moist, light brown -partially cemented -uncemented -partially cemented -uncemented, loose, very moist	3 min/ft
	41.5	10	SPT	2-3-3	6	0		SC		3 min/ft
1996										
	45.0									3 min/ft
	46.5	11	RING	7-13-9	22	100	G, A, UU		-medium dense	3 min/ft
1992										
	50.0									3 min/ft
	50.8	12	SPT	19-50/3"	R	100		SM	Silty SAND, few gravel, very dense, moist, light brown	3 min/ft
1988								CAL	CALICHE, hard, dry, light brown	
	55.0								Sandy lean CLAY, partially cemented, very moist, brown -uncemented, few caliche nodules	ppt=1.75 tsf
1984	56.5	13	RING	7-12-18	30	100	DD, M, A, C	CL	-very stiff	ppt=1.75 tsf
1980	60.0									

EXPLORATION LOG

SHEET 3 OF 4



START DATE: 03/22/19

END DATE: 03/25/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'28.38353" LONGITUDE W115°10'50.20417"

BORING B-19-10

PROJECT No. G-17-162

GROUND ELEV. 2039.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/22/19	21	2018.4
03/25/19	19.5	2019.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1976	61.5	14	SPT	3-4-7	11	100		CL	Sandy lean CLAY, few caliche nodules, stiff, very moist, brown	
	65.0								-with gravel (caliche nodules)	
1972	66.5	15	RING	4-6-11	17	100	A, UU	CH	Sandy fat CLAY with gravel (caliche nodules), stiff, very moist, brown	ppt=0.75 tsf
	70.0								-very stiff	ppt=1.0 tsf
1968	71.5	16	SPT	7-9-7	16	100		CH		
	75.0									
1964	76.3	17	RING	14-19-50/4"	R	100	G, A	SM	Silty SAND with gravel (caliche nodules), very dense, moist, light brown -partially cemented	
	80.0								Lean CLAY with sand, few caliche nodules, moist, brown	
1960	81.5	18	SPT	1-5-10	15	100		CL	-very stiff	ppt=1.0 tsf
	85.0									
1956	86.5	19	RING	5-10-16	26	100	A	CL	-light gray-brown, very stiff	ppt=1.0 tsf
	90.0									

EXPLORATION LOG

SHEET 4 OF 4



START DATE: 03/22/19

END DATE: 03/25/19

JOB DESCRIPTION I-15 & TROPICANA BRIDGES

LATITUDE N36°06'28.38353" LONGITUDE W115°10'50.20417"

BORING B-19-10

PROJECT No. G-17-162

GROUND ELEV. 2039.4

HAMMER DROP SYSTEM Auto (ETR=70.3)

DRILLING 8-inch O.D. Hollow Stem Augers

METHOD _____

EQUIPMENT CME 85

DRILLING COMPANY Cascade

OPERATOR M. Cain

ENGINEER J. Scheffner

BACKFILLED with CLSM DATE 03/29/19

GROUNDWATER LEVEL		
DATE	DEPTH ft	ELEV. ft
03/22/19	21	2018.4
03/25/19	19.5	2019.9

ELEV. (ft.)	DEPTH (ft)	SAMPLE		BLOW COUNT		Percent Recov'd	LAB TESTS	USCS Group	MATERIAL DESCRIPTION	REMARKS
		NO.	TYPE	6 Inch Increments	Last foot					
1948	91.5	20	SPT	3-4-5	9	100		CL	Lean CLAY with sand, trace caliche nodules, stiff, very moist, light brown	ppt=1.0 tsf
									94.00	
1944	95.0 95.3	21	RING	50/3"	R	0		SC	Clayey SAND, partially cemented, very dense, slightly moist, light gray	
								CAL	95.50 96.00 CALICHE, moderately hard, dry, light gray	
								CH	Sandy fat CLAY, few caliche nodules, moist, brown	
1940	100.0								-hard	ppt=1.5 tsf
	101.5	22	SPT	1-40-33	73	100			101.50	
									Bottom of boring at 101.5 feet	
1936										
1932										
1928										
1924										
1920										

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS	
			GRAPH	LETTER		
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS	CLEAN GRAVELS (LITTLE OR NO FINES)		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES	
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES	
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES	
	SAND AND SANDY SOILS	CLEAN SANDS (LITTLE OR NO FINES)		SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	
		CLEAN SANDS (LITTLE OR NO FINES)		SP	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES	
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)		SM	SILTY SANDS, SAND - SILT MIXTURES	
FINE GRAINED SOILS	SILTS AND CLAYS	LIQUID LIMIT LESS THAN 40		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
				CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
				OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
	SILTS AND CLAYS	LIQUID LIMIT GREATER THAN 50		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS	
				CH	INORGANIC CLAYS OF HIGH PLASTICITY	
				OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS	
NOVA GEOTECHNICAL & INSPECTION SERVICES	CLIENT: BEC Environmental				Materials Classification	
	PROJECT: I-15 & Tropicana Bridges					
					G-17-162	11a

LEGEND OF LABORATORY TESTS

- A Liquid & Plastic Limits
- C Consolidation
- Ch Chemical
- DD Dry Density
- DS Direct Shear
- G Grain Size
- M Moisture
- P Compaction
- R Resistivity
- RV R-Value
- S Swell
- Sol Solubility
- UU Triaxial
- UC Unconfined Compression

NOVA GEOTECHNICAL & INSPECTION SERVICES	CLIENT: BEC Environmental		
	PROJECT: I-15 & Tropicana Bridges	PROJECT NO.: G-17-162	PLATE NO.: 11b

BORING LOG KEY

Coarse-Grained Soils

<u>SPT N₆₀ Value</u>	<u>Apparent Density</u>
0-4	Very Loose
5-10	Loose
11-30	Medium Dense
31-50	Dense
>50	Very Dense

Fine-Grained Soils

<u>SPT N₆₀ Value</u>	<u>Consistency</u>
0-1	Very Soft
2-4	Soft
5-8	Medium Stiff
9-15	Stiff
16-30	Very Stiff
>30	Hard

$$N_{60} = N_{\text{measured}} * (\text{ETR}/60)$$

ETR = Hammer Energy Ratio (%)

Samplers

RING: 2.5-inch I.D. Modified California Sampler
SPT: 2-inch O.D. Split-Barrel Sampler
TUBE: 3-inch O.D. Shelby Tube

Abbreviations

ppt = pocket penetrometer
tsf = tons per square foot
min/ft = minutes per foot

NOVA GEOTECHNICAL & INSPECTION SERVICES	CLIENT: BEC Environmental		
	PROJECT: I-15 & Tropicana Bridges	PROJECT NO.: G-17-162	PLATE NO.: 11c



APPENDIX D

LABORATORY TEST RESULTS

Laboratory Test Results

I-15 & Tropicana

PERCENT PASSING NO. 200 SIEVE

SAMPLE LOCATION		% PASSING NO. 200 SIEVE
Boring	Depth	
B-19-01	60 ft.	18
B-19-04	111 ft.	40
B-19-07	76 ft.	47
B-19-08	26 ft.	30
B-19-08	105 ft.	34

ATTERBERG LIMITS

SAMPLE LOCATION		LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX
Boring	Depth			
B-19-04	95 ft.	28	14	14
	115 ft.	34	15	19
B-19-05	4-8 ft.	24	13	11
	15.5 ft.	NV	NP	NP
	55 ft.	NV	NP	NP
B-19-07	60 ft.	23	14	9
B-19-09	20 ft.	18	12	6

I-15 & Tropicana

MOISTURE CONTENT AND UNIT WEIGHT


SAMPLE LOCATION		MOISTURE (%)	DRY DENSITY (pcf)
Boring	Depth		
B-19-01	10 ft.	10	-
	40 ft.	27	-
	50 ft.	34	-
	60 ft.	21	-
B-19-02	6 ft.	11	118
	50.5 ft.	20	109
	55 ft.	17	-
	86 ft.	23	-
	91.5 ft.	10	-
B-19-03	6 ft.	12	119
	45 ft.	20	-
	92 ft.	31	-
B-19-04	5 ft.	7	-
	10 ft.	8	-
	40 ft.	26	-
	55 ft.	18	-
	95 ft.	27	-
	101 ft.	28	93
	111 ft.	24	103
	115 ft.	32	-

I-15 & Tropicana

SAMPLE LOCATION		MOISTURE (%)	DRY DENSITY (pcf)
Boring	Depth		
B-19-05	15.5 ft.	22	-
	35 ft.	14	-
	51 ft.	26	101
	55 ft.	24	-
	67 ft.	20	-
	96 ft.	25	104
	100 ft.	25	-
	111.5 ft.	23	-
B-19-06	6 ft.	11	114
	21 ft.	7	129
	55 ft.	21	-
B-19-07	10 ft.	9	-
	26 ft.	19	114
	36 ft.	25	94
	60 ft.	18	-
	66 ft.	18	-
B-19-08	5 ft.	9	-
	26 ft.	21	110
B-19-09	8.5 ft.	9	118
	20 ft.	11	-
B-19-10	30 ft.	25	-

ATTERBERG LIMITS RESULTS

ASTM D4318



Boring ID	Depth	LL	PL	PI	Fines	USCS	Description
● B-19-01	25 - 25.5	36	17	19	54	CL	SANDY LEAN CLAY
⊠ B-19-01	85 - 86.5	34	16	18			
▲ B-19-02	10 - 11	24	15	9	41	SC	CLAYEY SAND
★ B-19-02	20 - 21	29	16	13	60	CL	SANDY LEAN CLAY
⊕ B-19-02	40 - 41	39	16	23	44	GC	CLAYEY GRAVEL with SAND
⊕ B-19-02	70 - 71	52	19	33			
○ B-19-02	85 - 86.2	41	18	23			
△ B-19-03	20 - 21.5	29	15	14			
⊗ B-19-03	30 - 31.5	21	17	4			
⊕ B-19-03	60 - 61.5	41	18	23			
□ B-19-03	70 - 71	26	20	6	18	SC-SM	SILTY, CLAYEY SAND with GRAVEL
⊕ B-19-03	80 - 82.2	60	19	41			
⊕ B-19-04	25 - 26	42	24	18	54	CL	SANDY LEAN CLAY
★ B-19-04	35 - 36	23	18	5			
⊗ B-19-04	60 - 61	34	15	19			
■ B-19-04	90 - 91	37	14	23			
◆ B-19-05	25 - 26.5	24	16	8			
◇ B-19-05	60.5 - 61.5	90	27	63			
⊗ B-19-05	70 - 71.5	40	16	24			
⊕ B-19-05	90 - 92	27	16	11			

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. ATTERBERG LIMITS 65191074.GPJ TERRACON2015.GDT 8/22/19

PROJECT: I-15 and Tropicana TI
Reconstruction and Harmon
Ave HOV Ramp

SITE:
Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
Las Vegas, Nevada

EXHIBIT:

ATTERBERG LIMITS RESULTS

ASTM D4318




LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. ATTERBERG LIMITS 65191074.GPJ TERRACON2015.GDT 8/22/19

Boring ID	Depth	LL	PL	PI	Fines	USCS	Description
● B-19-06	90 - 92	41	20	21			
⊠ B-19-07	45 - 46	40	23	17	22	SC	CLAYEY SAND with GRAVEL
▲ B-19-07	80 - 80.8	26	18	8			
★ B-19-07	95 - 97	43	23	20			
⊙ B-19-08	35 - 36	64	25	39	30	SC	CLAYEY SAND
⊕ B-19-08	55 - 56	28	18	10			
○ B-19-08	75 - 76	28	16	12			
△ B-19-09	45 - 46	37	18	19			
⊗ B-19-10	7.5	23	19	4	53	CL-ML	SANDY SILTY CLAY
⊕ B-19-10	45	28	18	10	32	SC	CLAYEY SAND
⊠ B-19-10	55	35	19	16			
⊕ B-19-10	65	72	30	42			
⊕ B-19-10	85	33	15	18			

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp	 4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada
SITE: Las Vegas, Nevada		EXHIBIT:

LIQUID AND PLASTIC LIMITS TEST REPORT



Symbol	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Clayey SAND with gravel	24	13	11	57	38	SC
■	Sandy lean CLAY	30	16	14	87	51	CL
▲	Clayey GRAVEL with sand	35	15	20	59	47	GC

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL

Project: I-15 & TROPICANA BRIDGES


● **Source of Sample:** B-19-01 **Depth:** 6 to 10 ft.
 ■ **Source of Sample:** B-19-01 **Depth:** 50
 ▲ **Source of Sample:** B-19-01 **Depth:** 66

**Nova Geotechnical
and Inspection Services
Las Vegas, Nevada**

Remarks:

Plate 1

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Silty SAND	21	NP	NP	83	33	SM
■	Silty SAND	NV	NP	NP	80	36	SM
▲	Silty SAND with gravel	NV	NP	NP	79	39	SM


Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES

● **Source of Sample:** B-19-02 **Depth:** 6
 ■ **Source of Sample:** B-19-02 **Depth:** 55
 ▲ **Source of Sample:** B-19-02 **Depth:** 81

Remarks:

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Clayey SAND	20	12	8	75	42	SC
■	Clayey SAND with gravel	37	24	13	45	31	SC
▲	Silty SAND with gravel	NV	NP	NP	69	23	SM
◆	Silty SAND	NV	NP	NP	98	48	SM

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL


Project: I-15 & TROPICANA BRIDGES

- **Source of Sample:** B-19-03 **Depth:** 6
- **Source of Sample:** B-19-03 **Depth:** 45
- ▲ **Source of Sample:** B-19-03 **Depth:** 86
- ◆ **Source of Sample:** B-19-03 **Depth:** 92

**Nova Geotechnical
and Inspection Services
Las Vegas, Nevada**

Remarks:

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Clayey SAND	31	20	11	85	37	SC
■	Sandy silty CLAY	23	19	4	93	59	CL-ML
▲	Sandy lean CLAY	28	14	14			
◆	Sandy lean CLAY	34	15	19			

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES


● Source of Sample: B-19-04 **Depth:** 40
■ Source of Sample: B-19-04 **Depth:** 71
▲ Source of Sample: B-19-04 **Depth:** 95
◆ Source of Sample: B-19-04 **Depth:** 115

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

Remarks:

Plate 4

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Lean CLAY with sand	24	13	11			
■	Silty SAND	NV	NP	NP			
▲	Clayey SAND	25	16	9	77	49	SC
◆	Silty SAND	NV	NP	NP			
▼	Sandy lean CLAY with gravel	33	16	17	62	51	CL

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL

Project: I-15 & TROPICANA BRIDGES


● **Source of Sample:** B-19-05 **Depth:** 4 to 8 ft.
 ■ **Source of Sample:** B-19-05 **Depth:** 15.5
 ▲ **Source of Sample:** B-19-05 **Depth:** 35
 ◆ **Source of Sample:** B-19-05 **Depth:** 55
 ▼ **Source of Sample:** B-19-05 **Depth:** 100

**Nova Geotechnical
and Inspection Services
Las Vegas, Nevada**

Remarks:

Plate 5

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Silty SAND	NV	NP	NP	79	38	SM
■	Silty SAND with gravel	18	15	3	53	29	SM
▲	Silty SAND	NV	NP	NP	92	27	SM
◆	Clayey SAND with gravel	32	18	14	61	24	SC
▼	Sandy lean CLAY	29	17	12	87	51	CL

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES


● Source of Sample: B-19-06 **Depth:** 6
■ Source of Sample: B-19-06 **Depth:** 21
▲ Source of Sample: B-19-06 **Depth:** 41
◆ Source of Sample: B-19-06 **Depth:** 55
▼ Source of Sample: B-19-06 **Depth:** 75

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

Remarks:

Plate 6

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Silty, clayey SAND	22	16	6	74	41	SC-SM
■	Clayey SAND with gravel	58	23	35	62	43	SC
▲	Sandy lean CLAY	23	14	9			
◆	Sandy SILT	NV	NP	NP	96	69	ML

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES


● **Source of Sample:** B-19-07 **Depth:** 10
 ■ **Source of Sample:** B-19-07 **Depth:** 36
 ▲ **Source of Sample:** B-19-07 **Depth:** 60
 ◆ **Source of Sample:** B-19-07 **Depth:** 66

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

Remarks:

Plate 7

LIQUID AND PLASTIC LIMITS TEST REPORT




MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
● Silty SAND	NV	NP	NP	94	30	SM

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES
● Source of Sample: B-19-08 **Depth:** 26

Remarks:

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Clayey SAND	23	13	10	84	48	SC
■	Sandy silty CLAY	18	12	6			
▲	Silty SAND	NV	NP	NP	86	26	SM
◆	Clayey SAND	59	25	34	70	44	SC

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL
Project: I-15 & TROPICANA BRIDGES


● Source of Sample: B-19-09 **Depth:** 4 to 8 ft.
■ Source of Sample: B-19-09 **Depth:** 20
▲ Source of Sample: B-19-09 **Depth:** 30
◆ Source of Sample: B-19-09 **Depth:** 50

**Nova Geotechnical
 and Inspection Services
 Las Vegas, Nevada**

Remarks:

Plate 9

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Sandy lean CLAY	23	15	8	85	60	CL
■	Clayey SAND	35	19	16	89	36	SC
▲	Silty SAND with gravel	NV	NP	NP	71	37	SM

Project No. G-17-162 **Client:** BEC ENVIRONMENTAL

Project: I-15 & TROPICANA BRIDGES

● **Source of Sample:** B-19-10 **Depth:** 5 to 8 ft.
 ■ **Source of Sample:** B-19-10 **Depth:** 30
 ▲ **Source of Sample:** B-19-10 **Depth:** 76


**Nova Geotechnical
and Inspection Services
Las Vegas, Nevada**

Remarks:

Plate 10

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	


Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-01	25 - 25.5	SANDY LEAN CLAY (CL)		36	17	19		

Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-01	25 - 25.5	12.5	0.098			4.4	42.0		53.7	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

Particle Size Distribution Report



% +3"	% Gravel	% Sand	% Silt	% Clay
0	7	42	28	23

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/4"	100		
1/2"	100		
3/8"	98		
#4	93		
#8	91		
#10	89		
#16	89		
#30	89		
#40	87		
#50	85		
#100	66		
#200	51		

Material Description

Sandy lean CLAY

Atterberg Limits

PL= 16 LL= 30 PI= 14

Coefficients

D₉₀= 2.1138 D₈₅= 0.3020 D₆₀= 0.1182
D₅₀= 0.0724 D₃₀= 0.0095 D₁₅= 0.0025
D₁₀= C_u= C_c=

Classification

USCS= CL AASHTO= A-6(4)

Remarks

* (no specification provided)


Source of Sample: B-19-01 **Depth:** 50 **Date:** 5/3/19

Nova Geotechnical and Inspection Services Las Vegas, Nevada	Client: BEC ENVIRONMENTAL Project: I-15 & TROPICANA BRIDGES Project No: G-17-162 Plate
--	--

Tested By: DP **Checked By:** JS

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-02	10 - 11	CLAYEY SAND (SC)		24	15	9		


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-02	10 - 11	19	0.286			7.7	51.1		41.2	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

<p>PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp</p> <p>SITE: Las Vegas, Nevada</p>	<p>4685 S Ash Ave Ste H-4 Tempe, AZ</p>	<p>PROJECT NUMBER: 65191074</p> <p>CLIENT: BEC Environmental, Inc. Las Vegas, Nevada</p> <p>EXHIBIT:</p>
---	---	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-02	20 - 21	SANDY LEAN CLAY (CL)		29	16	13		


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-02	20 - 21	19				6.2	33.8		60.1	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-02	40 - 41	CLAYEY GRAVEL with SAND (GC)		39	16	23		

Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-02	40 - 41	37.5	3.082	0.027		34.6	21.5	26.5		17.3

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI
Reconstruction and Harmon
Ave HOV Ramp

SITE:
Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
Las Vegas, Nevada

EXHIBIT:

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY				
	coarse	fine	coarse	medium	fine					

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-03	70 - 71	SILTY, CLAYEY SAND with GRAVEL (SC-SM)		26	20	6		

Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-03	70 - 71	31.5	3.885	0.141		36.0	45.6		18.4	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI
Reconstruction and Harmon
Ave HOV Ramp

SITE:
Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
Las Vegas, Nevada

EXHIBIT:

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-04	25 - 26	SANDY LEAN CLAY (CL)		42	24	18		


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-04	25 - 26	12.5	0.093			1.6	44.7		53.7	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	<p style="font-size: small;">4685 S Ash Ave Ste H-4 Tempe, AZ</p>	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	---	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-05	5 - 6.5							


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-05	5 - 6.5	9.5				0.5	26.9		72.6	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	


LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

Boring ID	Depth	USCS Classification				WC (%)	LL	PL	PI	Cc	Cu
● B-19-06	10 - 11										
Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay	
● B-19-06	10 - 11	37.5	0.253			27.6	38.1		34.3		

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY			
	coarse	fine	coarse	medium	fine				


Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu		
● B-19-07	45 - 46	CLAYEY SAND with GRAVEL (SC)		40	23	17				
Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-07	45 - 46	25	2.191	0.097		37.7	40.1		22.2	

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY			
	coarse	fine	coarse	medium	fine				

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-08	35 - 36	CLAYEY SAND (SC)		64	25	39		

Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-08	35 - 36	0.075				0.0	0.0		30.0	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI
Reconstruction and Harmon
Ave HOV Ramp

SITE:
Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
Las Vegas, Nevada

EXHIBIT:

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-09	15 - 16							


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-09	15 - 16	19				6.2	22.9		70.9	

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-10	7.5	SANDY SILTY CLAY (CL-ML)		23	19	4		


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-10	7.5	12.5	0.102			2.5	44.5		53.0	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	-------------------------------------	--

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	


Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-19-10	45	CLAYEY SAND (SC)		28	18	10		

Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-19-10	45	4.75	0.132			0.0	68.1		31.9	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 5/30/19

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	<p style="font-size: small;">4685 S Ash Ave Ste H-4 Tempe, AZ</p>	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT:
---	---	--

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	89.94		
Ult. Stress, psi	90.16		
Cell pressure, psi	41.60		
Strain rate, in./min.	0.050		
Water content, %	13.1		
Wet density, pcf	138.4		
Dry density, pcf	122.3		
Saturation, %	93.7		
Void ratio	0.3781		
Specimen diameter, in.	2.39		
Specimen height, in.	5.03		
Height/diameter ratio	2.10		

Description: SC

LL = **PL =** **PI =** **Assumed GS= 2.7** **Type: Ring**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 55</p> <p>Sample Number: B-19-01</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	26.34		
Ult. Stress, psi	26.52		
Cell pressure, psi	62.30		
Strain rate, in./min.	0.055		
Water content, %	23.2		
Wet density, pcf	126.4		
Dry density, pcf	102.6		
Saturation, %	97.5		
Void ratio	0.6432		
Specimen diameter, in.	2.88		
Specimen height, in.	5.54		
Height/diameter ratio	1.92		

Description: CL

LL = 34 **PL = 16** **PI = 18** **Assumed GS= 2.7** **Type: Tube**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 85</p> <p>Sample Number: B-19-01</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	15.16		
Ult. Stress, psi	14.00		
Cell pressure, psi	17.36		
Strain rate, in./min.	0.050		
Water content, %	21.4		
Wet density, pcf	128.1		
Dry density, pcf	105.5		
Saturation, %	96.6		
Void ratio	0.5973		
Specimen diameter, in.	2.40		
Specimen height, in.	4.97		
Height/diameter ratio	2.07		

Description: CL

LL = 29 **PL = 16** **PI = 13** **Assumed GS= 2.7** **Type: Ring**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 20</p> <p>Sample Number: B-19-02</p> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	30.27		
Ult. Stress, psi	28.15		
Cell pressure, psi	27.78		
Strain rate, in./min.	0.050		
Water content, %	17.3		
Wet density, pcf	132.5		
Dry density, pcf	113.0		
Saturation, %	94.9		
Void ratio	0.4918		
Specimen diameter, in.	2.40		
Specimen height, in.	4.98		
Height/diameter ratio	2.07		

Description: GC

LL = 39	PL = 16	PI = 23	Assumed GS= 2.7	Type: Ring
---------	---------	---------	-----------------	------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 40</p> <p>Sample Number: B-19-02</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	10.78		
Ult. Stress, psi	10.30		
Cell pressure, psi	48.55		
Strain rate, in./min.	0.051		
Water content, %	36.0		
Wet density, pcf	115.7		
Dry density, pcf	85.1		
Saturation, %	98.9		
Void ratio	0.9817		
Specimen diameter, in.	2.39		
Specimen height, in.	5.01		
Height/diameter ratio	2.09		

Description: CH

LL = 52

PL = 19

PI = 33

Assumed GS= 2.7

Type: Ring

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 70


Sample Number: B-19-02

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	29.79		
Ult. Stress, psi	31.48		
Cell pressure, psi	62.38		
Strain rate, in./min.	0.058		
Water content, %	22.6		
Wet density, pcf	127.4		
Dry density, pcf	103.9		
Saturation, %	98.1		
Void ratio	0.6219		
Specimen diameter, in.	2.85		
Specimen height, in.	5.81		
Height/diameter ratio	2.04		

Description: CL

LL = 41

PL = 18

PI = 23

Assumed GS= 2.7

Type: Tube

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: Depth: 85


Sample Number: B-19-02

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	70.98		
Ult. Stress, psi	71.17		
Cell pressure, psi	20.74		
Strain rate, in./min.	0.050		
Water content, %	12.3		
Wet density, pcf	139.2		
Dry density, pcf	123.9		
Saturation, %	92.4		
Void ratio	0.3601		
Specimen diameter, in.	2.41		
Specimen height, in.	5.00		
Height/diameter ratio	2.08		

Description: CL

LL = 21

PL = 17

PI = 4

Assumed GS= 2.7

Type: Ring

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 30


Sample Number: B-19-03

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1			
Fail. Stress @ 15%, psi	7.17			
Ult. Stress, psi	12.74			
Cell pressure, psi	48.48			
Strain rate, in./min.	0.049			
Water content, %	11.6			
Wet density, pcf	147.0			
Dry density, pcf	131.8			
Saturation, %	99.5			
Void ratio	0.3267			
Specimen diameter, in.	2.40			
Specimen height, in.	4.94			
Height/diameter ratio	2.06			

Description: SC-SM

LL = 26	PL = 20	PI = 6	Assumed GS= 2.8	Type: Ring
----------------	----------------	---------------	------------------------	-------------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Note: Sample contained calcite nodules in fat clay matrix</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 70</p> <p>Sample Number: B-19-03</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	10.93		
Ult. Stress, psi	10.82		
Cell pressure, psi	55.56		
Strain rate, in./min.	0.058		
Water content, %	48.4		
Wet density, pcf	107.3		
Dry density, pcf	72.3		
Saturation, %	98.1		
Void ratio	1.3318		
Specimen diameter, in.	2.87		
Specimen height, in.	5.78		
Height/diameter ratio	2.01		

Description: CH

LL = 60	PL = 19	PI = 41	Assumed GS= 2.7	Type: Tube
---------	---------	---------	-----------------	------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 80</p> <p>Sample Number: B-19-03</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	47.59		
Ult. Stress, psi	45.60		
Cell pressure, psi	41.56		
Strain rate, in./min.	0.050		
Water content, %	19.4		
Wet density, pcf	131.4		
Dry density, pcf	110.0		
Saturation, %	98.7		
Void ratio	0.5317		
Specimen diameter, in.	2.42		
Specimen height, in.	4.98		
Height/diameter ratio	2.06		

Description: CL

LL = 34

PL = 15

PI = 19

Assumed GS= 2.7

Type: Ring

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 60


Sample Number: B-19-04

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	18.10		
Ult. Stress, psi	18.17		
Cell pressure, psi	62.44		
Strain rate, in./min.	0.050		
Water content, %	25.9		
Wet density, pcf	125.7		
Dry density, pcf	99.8		
Saturation, %	96.4		
Void ratio	0.7507		
Specimen diameter, in.	2.40		
Specimen height, in.	4.98		
Height/diameter ratio	2.07		


Description: CL

LL = 37 **PL = 14** **PI = 23** **Assumed GS= 2.8** **Type: Tube**

Project No.: 65191074
Date Sampled:
Remarks:
 Test performed per AASHTO T-296
 Note: Sample contained calcite nodules in fat clay matrix

Client: BEC Environmental Inc
Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
Source of Sample: **Depth:** 90
Sample Number: B-19-04
 UNCONSOLIDATED UNDRAINED TEST
 Terracon Consultants, Inc.
 Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	22.80		
Ult. Stress, psi	22.66		
Cell pressure, psi	41.56		
Strain rate, in./min.	0.049		
Water content, %	43.1		
Wet density, pcf	110.2		
Dry density, pcf	77.0		
Saturation, %	97.9		
Void ratio	1.1891		
Specimen diameter, in.	2.40		
Specimen height, in.	4.95		
Height/diameter ratio	2.06		

Description: CH

LL = 90 **PL = 27** **PI = 63** **Assumed GS= 2.7** **Type: Ring**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 60.5</p> <p>Sample Number: B-19-05</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1			
Fail. Stress @ 15%, psi	12.30			
Ult. Stress, psi	12.09			
Cell pressure, psi	48.51			
Strain rate, in./min.	0.050			
Water content, %	25.6			
Wet density, pcf	123.8			
Dry density, pcf	98.6			
Saturation, %	97.4			
Void ratio	0.7095			
Specimen diameter, in.	2.39			
Specimen height, in.	4.99			
Height/diameter ratio	2.09			

Description: CL

LL = 40	PL = 16	PI = 24	Assumed GS= 2.7	Type: Ring
---------	---------	---------	-----------------	------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 70</p> <p>Sample Number: B-19-05</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	50.57		
Ult. Stress, psi	48.90		
Cell pressure, psi	62.32		
Strain rate, in./min.	0.058		
Water content, %	20.5		
Wet density, pcf	129.3		
Dry density, pcf	107.3		
Saturation, %	97.0		
Void ratio	0.5714		
Specimen diameter, in.	2.87		
Specimen height, in.	5.81		
Height/diameter ratio	2.03		

Description: CL

LL = 27 PL = 16 PI = 11 Assumed GS= 2.7 Type: Tube

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Client: BEC Environmental Inc


Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 90

Sample Number: B-19-05

UNCONSOLIDATED UNDRAINED TEST
Terracon Consultants, Inc.
Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	7.28		
Ult. Stress, psi	6.42		
Cell pressure, psi	69.29		
Strain rate, in./min.	0.056		
Water content, %	25.9		
Wet density, pcf	120.8		
Dry density, pcf	96.0		
Saturation, %	92.5		
Void ratio	0.7559		
Specimen diameter, in.	2.85		
Specimen height, in.	5.59		
Height/diameter ratio	1.96		

Description: CL

LL = 41

PL = 20

PI = 21

Assumed GS= 2.7

Type: Tube

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296

Calcite nodules in sample

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 90


Sample Number: B-19-06

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	11.40		
Ult. Stress, psi	9.61		
Cell pressure, psi	62.34		
Strain rate, in./min.	0.059		
Water content, %	26.2		
Wet density, pcf	123.8		
Dry density, pcf	98.1		
Saturation, %	98.6		
Void ratio	0.7180		
Specimen diameter, in.	2.85		
Specimen height, in.	5.95		
Height/diameter ratio	2.09		

Description: CL

LL = 26 **PL = 18** **PI = 8** **Assumed GS= 2.7** **Type: Ring**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Calcite nodules in sample</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 80</p> <p>Sample Number: B-19-07</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	21.23		
Ult. Stress, psi	22.06		
Cell pressure, psi	27.78		
Strain rate, in./min.	0.050		
Water content, %	28.4		
Wet density, pcf	120.6		
Dry density, pcf	94.0		
Saturation, %	96.5		
Void ratio	0.7940		
Specimen diameter, in.	2.40		
Specimen height, in.	4.97		
Height/diameter ratio	2.07		

Description: SC

LL = 64 **PL = 25** **PI = 39** **Assumed GS= 2.7** **Type: Ring**

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Calcite nodules in sample</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 35</p> <p>Sample Number: B-19-08</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1			
Fail. Stress @ 15%, psi	27.79			
Ult. Stress, psi	25.62			
Cell pressure, psi	41.66			
Strain rate, in./min.	0.050			
Water content, %	20.4			
Wet density, pcf	128.7			
Dry density, pcf	106.9			
Saturation, %	95.5			
Void ratio	0.5774			
Specimen diameter, in.	2.40			
Specimen height, in.	5.02			
Height/diameter ratio	2.09			

Description: CL

LL = 28 PL = 18 PI = 10 Assumed GS= 2.7 Type: Ring

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Calcite nodule in sample</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 55</p> <p>Sample Number: B-19-08</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
---	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	22.70		
Ult. Stress, psi	20.80		
Cell pressure, psi	55.56		
Strain rate, in./min.	0.050		
Water content, %	19.5		
Wet density, pcf	134.2		
Dry density, pcf	112.3		
Saturation, %	98.0		
Void ratio	0.5560		
Specimen diameter, in.	2.39		
Specimen height, in.	4.95		
Height/diameter ratio	2.07		

Description: CL

LL = 28 PL = 16 PI = 12 Assumed GS= 2.8 Type: Ring

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 75</p> <p>Sample Number: B-19-08</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	24.54		
Ult. Stress, psi	24.07		
Cell pressure, psi	69.29		
Strain rate, in./min.	0.059		
Water content, %	25.0		
Wet density, pcf	123.5		
Dry density, pcf	98.8		
Saturation, %	95.7		
Void ratio	0.7052		
Specimen diameter, in.	2.85		
Specimen height, in.	5.89		
Height/diameter ratio	2.06		

Description: CL

LL = **PL =** **PI =** **Assumed GS= 2.7** **Type:** Tube

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Calcite nodules in sample</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 95</p> <p>Sample Number: B-19-08</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	42.44		
Ult. Stress, psi	42.05		
Cell pressure, psi	34.70		
Strain rate, in./min.	0.050		
Water content, %	19.7		
Wet density, pcf	132.8		
Dry density, pcf	111.0		
Saturation, %	95.9		
Void ratio	0.5749		
Specimen diameter, in.	2.39		
Specimen height, in.	4.96		
Height/diameter ratio	2.07		

Description: CL

LL = 37

PL = 18

PI = 19

Assumed GS= 2.8

Type: Ring

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296 Calcite nodules in sample

Client: BEC Environmental Inc

Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 45


Sample Number: B-19-09

UNCONSOLIDATED UNDRAINED TEST

Terracon Consultants, Inc.

Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	19.96		
Ult. Stress, psi	19.25		
Cell pressure, psi	48.52		
Strain rate, in./min.	0.053		
Water content, %	25.4		
Wet density, pcf	126.5		
Dry density, pcf	100.8		
Saturation, %	97.0		
Void ratio	0.7334		
Specimen diameter, in.	2.39		
Specimen height, in.	5.03		
Height/diameter ratio	2.10		

Description: CH

LL = **PL =** **PI =** **Assumed GS=** 2.8 **Type:** Ring

Project No.: 65191074

Date Sampled:

Remarks:

Test performed per AASHTO T-296 Calcite nodules in sample

Client: BEC Environmental Inc


Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

Source of Sample: **Depth:** 65

Sample Number: B-19-09

UNCONSOLIDATED UNDRAINED TEST
Terracon Consultants, Inc.
Tempe, AZ

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	37.90		
Ult. Stress, psi	33.38		
Cell pressure, psi	13.87		
Strain rate, in./min.	0.050		
Water content, %	13.1		
Wet density, pcf	138.1		
Dry density, pcf	122.1		
Saturation, %	92.9		
Void ratio	0.3802		
Specimen diameter, in.	2.40		
Specimen height, in.	4.96		
Height/diameter ratio	2.07		

Description: CL

LL =	PL =	PI =	Assumed GS= 2.7	Type: Ring
------	------	------	-----------------	------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 15</p> <p>Sample Number: B-19-10</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST




Sample No.	1		
Fail. Stress @ 15%, psi	16.17		
Ult. Stress, psi	14.66		
Cell pressure, psi	34.65		
Strain rate, in./min.	0.050		
Water content, %	25.7		
Wet density, pcf	146.5		
Dry density, pcf	116.6		
Saturation, %	144.0		
Void ratio	0.4991		
Specimen diameter, in.	2.38		
Specimen height, in.	4.95		
Height/diameter ratio	2.08		

Description: SC

LL = 28	PL = 18	PI = 10	Assumed GS= 2.8	Type: Ring
---------	---------	---------	-----------------	------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296 Note: Sample contained calcite nodule in clayey sand matrix</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 45</p> <p>Sample Number: B-19-10</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

UNCONSOLIDATED UNDRAINED TEST



Sample No.	1		
Fail. Stress @ 15%, psi	23.02		
Ult. Stress, psi	22.83		
Cell pressure, psi	48.52		
Strain rate, in./min.	0.050		
Water content, %	69.7		
Wet density, pcf	98.6		
Dry density, pcf	58.1		
Saturation, %	99.1		
Void ratio	1.9000		
Specimen diameter, in.	2.39		
Specimen height, in.	4.99		
Height/diameter ratio	2.09		

Description: CH

LL = 72	PL = 30	PI = 42	Assumed GS = 2.7	Type: Ring
----------------	----------------	----------------	-------------------------	-------------------

<p>Project No.: 65191074</p> <p>Date Sampled:</p> <p>Remarks: Test performed per AASHTO T-296</p>	<p>Client: BEC Environmental Inc</p> <p>Project: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project</p> <p>Source of Sample: Depth: 65</p> <p>Sample Number: B-19-10</p> <hr/> <p style="text-align: center;">UNCONSOLIDATED UNDRAINED TEST Terracon Consultants, Inc. Tempe, AZ</p>
--	---

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Sandy Lean Clay (CL)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-01 @ 25'	LAB NO:	B-19-01 @ 25'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	1000	2000	4000	Normal Stress (psf):	1000	2000	4000
Dry mass (g):	130.10	132.10	131.20	Dry mass (g):	130.10	132.10	131.20
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9964	0.9899	0.9808
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	18.4	18.5	19.1	Moisture, %:	21.8	21.3	20.4
Dry Density (pcf):	107.8	109.4	108.7	Dry Density (pcf):	108.2	110.5	110.8
Saturation, %:	91	96	97	Saturation, %:	109	113	110
Void Ratio:	0.54	0.51	0.52	Void Ratio:	0.53	0.50	0.49

	1000	2000	4000
Normal Stress (psf):	1000	2000	4000
Maximum Shear Stress, (psf):	1232	1878	2667
Displacement at Maximum Shear, (in):	0.062	0.071	0.087
Shear Stress at Max Displacement, (psf)	765	1375	2165
Maximum Displacement, (in):	0.450	0.451	0.450
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	25	838
AT MAX DISPLACEMENT	25	370

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Sandy Lean Clay (CL)
SAMPLE SOURCE: B-19-01 @ 25'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-01 @ 25'
DATE SAMPLED: 4/11/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Clayey Sand (SC)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-02 @ 10'	LAB NO:	B-19-02 @ 10'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	500	1000	2000	Normal Stress (psf):	500	1000	2000
Dry mass (g):	150.80	143.60	144.50	Dry mass (g):	150.80	143.60	144.50
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9982	0.9933	0.9875
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	9.5	14.1	13.4	Moisture, %:	13.5	16.7	16.0
Dry Density (pcf):	124.9	118.9	119.7	Dry Density (pcf):	125.1	119.7	121.2
Saturation, %:	78	95	92	Saturation, %:	111	116	116
Void Ratio:	0.33	0.39	0.38	Void Ratio:	0.32	0.38	0.37

	500	1000	2000
Normal Stress (psf):	500	1000	2000
Maximum Shear Stress, (psf):	1088	1328	2141
Displacement at Maximum Shear, (in):	0.031	0.048	0.092
Shear Stress at Max Displacement, (psf)	395	741	1567
Maximum Displacement, (in):	0.450	0.450	0.450
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	36	682
AT MAX DISPLACEMENT	38	0

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Clayey Sand (SC)
SAMPLE SOURCE: B-19-02 @ 10'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-02 @ 10'
DATE SAMPLED: 4/11/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Sandy Lean Clay (CL)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-03 @ 20'-21.5'	LAB NO:	B-19-03 @ 20'-21.5'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	1000	2000	4000	Normal Stress (psf):	1000	2000	4000
Dry mass (g):	140.90	145.60	140.40	Dry mass (g):	140.90	145.60	140.40
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9954	0.9911	0.9828
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	13.5	12.1	10.9	Moisture, %:	17.2	19.2	14.5
Dry Density (pcf):	116.7	120.6	116.3	Dry Density (pcf):	117.2	121.7	118.3
Saturation, %:	85	86	68	Saturation, %:	111	142	97
Void Ratio:	0.42	0.37	0.42	Void Ratio:	0.41	0.36	0.40

	1000	2000	4000
Normal Stress (psf):	1000	2000	4000
Maximum Shear Stress, (psf):	1208	2643	2882
Displacement at Maximum Shear, (in):	0.067	0.079	0.080
Shear Stress at Max Displacement, (psf)	682	2224	2308
Maximum Displacement, (in):	0.450	0.451	0.451
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	26	1089
AT MAX DISPLACEMENT	25	640

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested

Reviewed By: _____

DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project

JOB NO: 65191074



MATERIAL: Sandy Lean Clay (CL)

WORK ORDER NO: 65191074

SAMPLE SOURCE: B-19-03 @ 20'-21.5'

LAB NO: B-19-03 @ 20'-21.5'

DATE SAMPLED: 4/11/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Sandy Lean Clay (CL)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-04 @ 25'	LAB NO:	B-19-04 @ 25'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	1000	2000	4000	Normal Stress (psf):	1000	2000	4000
Dry mass (g):	114.10	115.60	118.70	Dry mass (g):	114.10	115.60	118.70
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9926	0.9875	0.9775
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	26.8	25.5	23.3	Moisture, %:	30.6	32.4	30.2
Dry Density (pcf):	94.5	95.7	98.3	Dry Density (pcf):	95.2	97.0	100.6
Saturation, %:	95	93	90	Saturation, %:	110	121	124
Void Ratio:	0.75	0.73	0.68	Void Ratio:	0.74	0.71	0.65

	1000	2000	4000
Normal Stress (psf):	1000	2000	4000
Maximum Shear Stress, (psf):	1256	2284	4748
Displacement at Maximum Shear, (in):	0.052	0.055	0.100
Shear Stress at Max Displacement, (psf)	753	1495	3935
Maximum Displacement, (in):	0.450	0.450	0.450
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	46	228
AT MAX DISPLACEMENT	37	11

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By:

DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Sandy Lean Clay (CL)
SAMPLE SOURCE: B-19-04 @ 25'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-04 @ 25'
DATE SAMPLED: 4/11/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Sandy Lean Clay (CL)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-05 @ 5'-6.5'	LAB NO:	B-19-05 @ 5'-6.5'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	500	1000	2000	Normal Stress (psf):	500	1000	2000
Dry mass (g):	139.60	145.20	147.30	Dry mass (g):	139.60	145.20	147.30
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9995	0.9973	0.9919
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	14.3	11.8	13.1	Moisture, %:	18.7	20.5	16.4
Dry Density (pcf):	115.6	120.3	122.0	Dry Density (pcf):	115.7	120.6	123.0
Saturation, %:	88	83	97	Saturation, %:	115	146	126
Void Ratio:	0.43	0.38	0.36	Void Ratio:	0.43	0.37	0.35

	500	1000	2000
Normal Stress (psf):	500	1000	2000
Maximum Shear Stress, (psf):	753	1591	2165
Displacement at Maximum Shear, (in):	0.071	0.049	0.062
Shear Stress at Max Displacement, (psf)	347	634	1232
Maximum Displacement, (in):	0.450	0.450	0.450
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	30	1017
AT MAX DISPLACEMENT	31	48

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Sandy Lean Clay (CL)
SAMPLE SOURCE: B-19-05 @ 5'-6.5'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-05 @ 5'-6.5'
DATE SAMPLED: 4/11/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Clayey Sand (SC)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-06 @ 10'	LAB NO:	B-19-06 @ 10'
		DATE SAMPLED:	04/24/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	500	1000	2000	Normal Stress (psf):	500	1000	2000
Dry mass (g):	143.60	144.30	142.70	Dry mass (g):	143.60	144.30	142.70
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9953	0.9849	0.9791
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	13.0	13.4	13.5	Moisture, %:	15.0	13.4	14.5
Dry Density (pcf):	118.9	119.5	118.2	Dry Density (pcf):	119.5	121.4	120.7
Saturation, %:	88	93	90	Saturation, %:	104	98	104
Void Ratio:	0.39	0.38	0.40	Void Ratio:	0.38	0.36	0.37

	500	1000	2000
Normal Stress (psf):	500	1000	2000
Maximum Shear Stress, (psf):	658	1029	1806
Displacement at Maximum Shear, (in):	0.054	0.121	0.106
Shear Stress at Max Displacement, (psf)	490	777	1399
Maximum Displacement, (in):	0.451	0.451	0.451
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	37	270
AT MAX DISPLACEMENT	31	179

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Clayey Sand (SC)
SAMPLE SOURCE: B-19-06 @ 10'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-06 @ 10'
DATE SAMPLED: 4/24/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Clayey Sand (SC)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-08 @ 7.5'	LAB NO:	B-19-08 @ 7.5'
		DATE SAMPLED:	04/24/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	500	1000	2000	Normal Stress (psf):	500	1000	2000
Dry mass (g):	135.40	134.70	133.80	Dry mass (g):	135.40	134.70	133.80
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9973	0.9914	0.9831
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	12.3	12.1	12.6	Moisture, %:	18.8	17.8	16.4
Dry Density (pcf):	112.1	111.6	110.8	Dry Density (pcf):	112.5	112.5	112.7
Saturation, %:	69	66	68	Saturation, %:	106	100	93
Void Ratio:	0.48	0.48	0.49	Void Ratio:	0.47	0.47	0.47

	500	1000	2000
Normal Stress (psf):	500	1000	2000
Maximum Shear Stress, (psf):	514	706	1399
Displacement at Maximum Shear, (in):	0.150	0.442	0.218
Shear Stress at Max Displacement, (psf)	466	706	1316
Maximum Displacement, (in):	0.450	0.451	0.451
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	31	168
AT MAX DISPLACEMENT	30	161

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Clayey Sand (SC)
SAMPLE SOURCE: B-19-08 @ 7.5'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-08 @ 7.5'
DATE SAMPLED: 4/24/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Clayey Sand (SC)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-09 @ 15'	LAB NO:	B-19-09 @ 15'
		DATE SAMPLED:	04/24/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	1000	2000	4000	Normal Stress (psf):	1000	2000	4000
Dry mass (g):	127.00	125.80	121.90	Dry mass (g):	127.00	125.80	121.90
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9953	0.9833	0.9771
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	20.8	20.3	21.1	Moisture, %:	23.9	23.4	25.0
Dry Density (pcf):	105.2	104.2	101.0	Dry Density (pcf):	105.7	106.0	103.3
Saturation, %:	96	92	87	Saturation, %:	112	110	110
Void Ratio:	0.57	0.59	0.64	Void Ratio:	0.57	0.56	0.60

	1000	2000	4000
Normal Stress (psf):	1000	2000	4000
Maximum Shear Stress, (psf):	1232	1937	3145
Displacement at Maximum Shear, (in):	0.032	0.071	0.111
Shear Stress at Max Displacement, (psf)	730	1399	2787
Maximum Displacement, (in):	0.450	0.451	0.451
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	32	628
AT MAX DISPLACEMENT	34	36

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080



PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Clayey Sand (SC)
SAMPLE SOURCE: B-19-09 @ 15'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-09 @ 15'
DATE SAMPLED: 4/24/2019



**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**



PROJECT:	I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project	JOB NO:	65191074
MATERIAL:	Sandy Silty Clay (CL-ML)	WORK ORDER NO:	65191074
SAMPLE SOURCE:	B-19-10 @ 7.5'	LAB NO:	B-19-10 @ 7.5'
		DATE SAMPLED:	04/11/19


Sample Preparation: Insitu density, material and moisture. Specimens consolidated at normal load for 30 mins. Prior to shear. Specimens inundated.

Initial Parameters of specimen:				Pre- Shear Parameters of specimen:			
	Point 1	Point 2	Point 3		Point 1	Point 2	Point 3
Normal Stress (psf):	500	1000	2000	Normal Stress (psf):	500	1000	2000
Dry mass (g):	121.70	121.90	128.00	Dry mass (g):	121.70	121.90	128.00
Height (in):	1.0000	1.0000	1.0000	Height (in):	0.9971	0.9919	0.9845
Diameter (in):	2.42	2.42	2.42	Diameter (in):	2.42	2.42	2.42
Moisture, %:	21.7	23.7	19.8	Moisture, %:	29.4	25.4	22.8
Dry Density (pcf):	100.8	101.0	106.0	Dry Density (pcf):	101.1	101.8	107.7
Saturation, %:	90	98	93	Saturation, %:	122	108	113
Void Ratio:	0.64	0.64	0.56	Void Ratio:	0.64	0.63	0.54

	500	1000	2000
Normal Stress (psf):	500	1000	2000
Maximum Shear Stress, (psf):	885	945	2284
Displacement at Maximum Shear, (in):	0.039	0.053	0.040
Shear Stress at Max Displacement, (psf)	419	682	1423
Maximum Displacement, (in):	0.450	0.451	0.450
Rate of Deformation, in/min	0.0070	0.0070	0.0070

	FRICITION ANGLE (°)	COHESION (psf)
AT MAX SHEAR STRESS	43	419
AT MAX DISPLACEMENT	34	49

SHEAR DEVICE: Geomatic model 8914, Dead Weight load force



Note: The friction angle presented is applicable only to the load ranges and sample conditions tested



Reviewed By: _____

**DIRECT SHEAR TEST OF SOILS UNDER CONSOLIDATED
DRAINED CONDITIONS ASTM D3080**




PROJECT: I-15 Tropicana Interchange Reconstruction & Harmon Ave HOV Ramp Project
MATERIAL: Sandy Silty Clay (CL-ML)
SAMPLE SOURCE: B-19-10 @ 7.5'

JOB NO: 65191074
WORK ORDER NO: 65191074
LAB NO: B-19-10 @ 7.5'
DATE SAMPLED: 4/11/2019



CONSOLIDATION TEST (D2435)

Per ASTM D2435/D2435M, Fig. 3



LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS_LOAD-DEF_PROP_STRESS-STRAIN_65191074.GPJ TERRACON_DATATEMPLATE.GDT 9/11/19

Natural		Initial Dry Density (pcf)	LL	PI	Sp. Gr.	Overburden (psf)	P _c (psf)	C _c (% / log stress)	C _u (% / log stress)	Initial Void Ratio
Saturation	Moisture									
89.9 %	30.1 %	88.5	41	23	2.70	100	4,989	18.603	2.704	0.906


MATERIAL DESCRIPTION									USCS	AASHTO
Sandy Lean Clay*										

NOTES: Assumed Specific Gravity.
*Material description based on visual-manual method ASTM D2488

Borehole: B-19-03 Depth: 60.001 ft Specimen #: 14.1

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada
---	-------------------------------------	--

Load No. = 7
 Load = 4000 psf
 $D_0 = 0.0045$
 $D_{90} = 0.0130$
 $D_{100} = 0.0139$
 $t_{90} = 0.40$ min.



$C_v @ t_{90}$
 5.157 ft²/day

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS. TIME-DEF. PROP. SORT-TIME 65191074.GPJ TERRACON_DATA_TEMPLATE.GDT 7/17/19

PROJECT: I-15 and Tropicana TI
 Reconstruction and Harmon
 Ave HOV Ramp
 SITE:
 Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
 Las Vegas, Nevada

EXHIBIT:

CONSOLIDATION TEST (D2435)

Per ASTM D2435/D2435M, Fig. 3



LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS_LOAD-DEF_PROP_STRESS-STRAIN 65191074.GPJ TERRACON_DATATEMPLATE.GDT 9/3/19


Natural		Initial Dry Density (pcf)	LL	PI	Sp. Gr.	Overburden (psf)	P _c (psf)	C _c (% / log stress)	C _u (% / log stress)	Initial Void Ratio
Saturation	Moisture									
82.1 %	24.2 %	93.9	40	17	2.70	100	3,511	10.896	1.609	0.795

MATERIAL DESCRIPTION								USCS	AASHTO
CLAYEY SAND with GRAVEL								SC	A-2-6

NOTES: Assumed Specific Gravity.

Borehole: B-19-07 Depth: 45.001 ft Specimen #: 11.1

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada EXHIBIT: B-2
---	-------------------------------------	--



Load No. = 7
 Load = 4000 psf
 $D_0 = 0.0084$
 $D_{90} = 0.0150$
 $D_{100} = 0.0157$
 $t_{90} = 0.72 \text{ min.}$

$C_v @ t_{90}$
 2.894 ft²/day

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS TIME-DEF PROP SORT-TIME 65191074.GPJ TERRACON DATATEMPLATE.GDT 7/17/19


PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp
SITE: Las Vegas, Nevada

Terracon
 4685 S Ash Ave Ste H-4
 Tempe, AZ

PROJECT NUMBER: 65191074
CLIENT: BEC Environmental, Inc. Las Vegas, Nevada
EXHIBIT:

CONSOLIDATION TEST (D2435)

Per ASTM D2435/D2435M, Fig. 3



LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS_LOAD-DEF_PROP_STRESS-STRAIN 65191074.GPJ TERRACON_DATATEMPLATE.GDT 9/11/19

Natural		Initial Dry Density (pcf)	LL	PI	Sp. Gr.	Overburden (psf)	P _c (psf)	C _c (% / log stress)	C _c (% / log stress)	Initial Void Ratio
Saturation	Moisture									
76.7 %	17.8 %	103.5	35	16	2.70	100	2,203	8.039	1.953	0.628

MATERIAL DESCRIPTION									USCS	AASHTO
Sandy Lean Clay*										


NOTES: Assumed Specific Gravity.
*Material description based on visual-manual method ASTM D2488

Borehole: B-19-10 Depth: 55.001 ft Specimen #: 13.1

PROJECT: I-15 and Tropicana TI Reconstruction and Harmon Ave HOV Ramp SITE: Las Vegas, Nevada	4685 S Ash Ave Ste H-4 Tempe, AZ	PROJECT NUMBER: 65191074 CLIENT: BEC Environmental, Inc. Las Vegas, Nevada
---	-------------------------------------	--

Borehole: B-19-10 Depth: 55.001 Specimen #: 13.1

Per ASTM D2435/D2435M, Fig. 2



Load No. = 7
Load = 4000 psf
 $D_0 = 0.0036$
 $D_{90} = 0.0100$
 $D_{100} = 0.0107$
 $t_{90} = 0.41$ min.

$C_v @ t_{90}$
5.135 ft²/day

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. CONS TIME-DEF PROP SORT-TIME 65191074.GPJ TERRACON DATATEMPLATE.GDT 7/17/19

PROJECT: I-15 and Tropicana TI
Reconstruction and Harmon
Ave HOV Ramp

SITE:
Las Vegas, Nevada




PROJECT NUMBER: 65191074

CLIENT: BEC Environmental, Inc.
Las Vegas, Nevada

EXHIBIT:

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - NV T115D

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	200	131.8	8.3	0.00	29	2.50	480	75	75
2	100	129.2	7.7	0.00	63	2.60	146	49	52
3	150	137.5	7.4	0.00	64	2.60	277	50	53

Test Results	Material Description
R-value at 300 psi exudation pressure = 54	Clayey SAND with gravel
Project No.: G-17-162 Project: I-15 & TROPICANA BRIDGES Source of Sample: B-19-01 Depth: 6 to 10 ft. Date: 8/14/2019	Tested by: DP Checked by: JS Remarks:
R-VALUE TEST REPORT <h1 style="margin: 0;">Nova Geotechnical</h1>	Plate 1

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - NV T115D

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	200	128.1	12.3	0.00	70	2.50	481	54	54
2	200	119.2	14.2	0.00	105	2.50	242	31	31
3	180	128.7	14.1	0.00	110	2.50	114	27	27

Test Results	Material Description
<p>R-value at 300 psi exudation pressure = 35</p>	<p>Lean CLAY with sand</p>
<p>Project No.: G-17-162 Project: I-15 & TROPICANA BRIDGES Source of Sample: B-19-05 Depth: 4 to 8 ft. Date: 8/14/2019</p>	<p>Tested by: DP Checked by: JS Remarks:</p>
<p>R-VALUE TEST REPORT</p> <h2 style="margin: 0;">Nova Geotechnical</h2>	

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - NV T115D

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	100	137.4	4.9	0.00	125	2.50	157	18	18
2	160	126.5	3.8	0.00	100	2.50	295	30	30
3	200	130.1	2.8	0.00	60	2.50	526	54	54

Test Results	Material Description
<p>R-value at 300 psi exudation pressure = 31</p>	<p>Clayey SAND</p>
<p>Project No.: G-17-162 Project: I-15 & TROPICANA BRIDGES Source of Sample: B-19-09 Depth: 4 to 8 ft. Date: 8/14/2019</p>	<p>Tested by: DP Checked by: JS Remarks:</p>
<p>R-VALUE TEST REPORT</p> <h2 style="margin: 0;">Nova Geotechnical</h2>	

R-VALUE TEST REPORT



Resistance R-Value and Expansion Pressure - NV T115D

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	200	132.4	10.5	0.00	83	2.50	389	45	45
2	200	130.8	10.1	0.00	35	2.30	557	74	70
3	180	127.3	11.0	0.00	95	2.60	189	34	36

Test Results	Material Description
<p>R-value at 300 psi exudation pressure = 39</p>	<p>Sandy lean CLAY</p>
<p>Project No.: G-17-162 Project: I-15 & TROPICANA BRIDGES Source of Sample: B-19-10 Depth: 5 to 8 ft. Date: 8/14/2019</p>	<p>Tested by: DP Checked by: JS Remarks:</p>
<p>R-VALUE TEST REPORT</p> <h2 style="margin: 0;">Nova Geotechnical</h2>	



Laboratory Analysis Report

Terracon
 Kirk Jackson
 4685 S. Ash Ave
 Suite H4
 Tempe, AZ 85282

Project: 65191074
 Date Received: 5/1/2019
 Date Reported: 9/11/2019
 PO Number: 65191074

Lab Number: 928467-1	B-19-2 (7.5)
-----------------------------	---------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.5	SU	
Sulfate, SO4	AASHTO T290	1,900	ppm	
Chloride, Cl	ASTM D 4327	17	ppm	

Lab Number: 928467-2	B-19-03 (7.5-9)
-----------------------------	------------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.5	SU	
Sulfate, SO4	AASHTO T290	2,700	ppm	
Chloride, Cl	ASTM D 4327	31	ppm	

Lab Number: 928467-3	B-19-04 (20)
-----------------------------	---------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.5	SU	
Sulfate, SO4	AASHTO T290	4,700	ppm	
Chloride, Cl	ASTM D 4327	94	ppm	

Lab Number: 928467-4	B-19-10 (5)
-----------------------------	--------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.3	SU	
Sulfate, SO4	AASHTO T290	4,400	ppm	
Chloride, Cl	ASTM D 4327	76	ppm	

Lab Number: 928467-5	B-19-05 (25-26.5)
-----------------------------	--------------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.3	SU	
Sulfate, SO4	AASHTO T290	380	ppm	
Chloride, Cl	ASTM D 4327	28	ppm	



Laboratory Analysis Report

Terracon
Kirk Jackson
4685 S. Ash Ave
Suite H4
Tempe, AZ 85282

Project: 65191074
Date Received: 5/1/2019
Date Reported: 9/11/2019
PO Number: 65191074

Lab Number: 928467-6 **B-19-01 (6-10)**

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.4	SU	
Resistivity	AASHTO T288	1060	ohm-cm	
Sulfate, SO4	AASHTO T290	2,500	ppm	
Chloride, Cl	ASTM D 4327	45	ppm	



Laboratory Analysis Report

Terracon
 Kirk Jackson
 4685 S. Ash Ave
 Suite H4
 Tempe, AZ 85282

Project: 65191074
 Date Received: 5/8/2019
 Date Reported: 9/11/2019
 PO Number: 65191074

Lab Number: 928544-1	B-19-09 (4-8)
-----------------------------	----------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.53	SU	
Resistivity	AASHTO T288	1828	ohm-cm	
Sulfate, SO4	AASHTO T290	1662	ppm	
Chloride, Cl	ASTM D 512	46	ppm	

Lab Number: 928544-2	B-19-08 (10)
-----------------------------	---------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.87	SU	
Sulfate, SO4	AASHTO T290	1033	ppm	
Chloride, Cl	ASTM D 512	156	ppm	

Lab Number: 928544-3	B-19-06 (7.5)
-----------------------------	----------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.46	SU	
Sulfate, SO4	AASHTO T290	1537	ppm	
Chloride, Cl	ASTM D 512	15	ppm	

Lab Number: 928544-4	B-19-07 (15)
-----------------------------	---------------------

<i>ASTM</i>	Method	Result	Units	Levels
pH	AASHTO T289	8.5	SU	
Sulfate, SO4	AASHTO T290	5080	ppm	
Chloride, Cl	ASTM D 512	70	ppm	



APPENDIX E

REFRACTION MICROTREMOR

SURVEY REPORT

Refraction Microtremor Survey Report

Introduction:

This report presents the results obtained from analysis of microtremor data acquired along two seismic profiles as part of the I-15 bridge replacement project in Las Vegas, Nevada. The sites are at Tropicana Ave and I-15 and Harmon Ave and I-15.

Data processing:

The microtremor data was acquired by NOVA Geotechnical and Inspection Services and provided to SubTerraSeis in SEG-Y format. Nine ambient noise data sets, each 30-second-long and sampled every 2 milliseconds acquired using 12 geophones, spaced 8m (26.25 ft) apart along a linear array were acquired at each site. This comprised the microtremor data which was then analyzed following the methodology enumerated by Louie (2001)¹ and explained in the following paragraphs.

First, the geometry (geophone spacing and elevation changes if present) are entered. Based on the p-tau transformation followed by a Fourier transform, each time-interval record from the survey is converted into slowness versus frequency (p-f) velocity spectral image. Effectively, the Rayleigh waves are separated, the fundamental mode identified and true phase velocity can be picked. Once all the p-f images for all the records have been screened for initial dispersion-curve formation, the individual p-f images can be combined, if necessary, to produce a composite p-f image of some or all the records.

Using an integrated picking tool, the lower bound of spectral dispersion curve of either the individual or composite p-f image are picked, making sure there is only one pick per frequency. Being that the final model will be based on an average of the picks made, only enough picks so that the general trend of the spectral curve is necessary. Furthermore, careful practice is essential during the picking phase so that no high or low velocity inversions are artificially imposed into the final model, and that artifacts aren't accidentally identified as part of the fundamental mode.

After all the appropriate picks have been made, the picks are then modeled using an inversion to form a shear-wave velocity (V_s) profile which shows velocity variations with depth. Figure 1 shows a schematic of this process. The site class per IBC 2006 Section

¹ Louie, J.N., (2001). Faster, Better: Shear-Wave Velocity to 100 Meters Depth From Refraction Microtremor Arrays. Bulletin of the Seismological Society of America, 2001, v. 91, no. 2 (April), p.347-364.

1613.5.5. is then determined from time averaged shear-wave values down to 100 ft depth using the equation (16-41) in the IBC 2006 code book.




Figure 1: Schematic showing the steps involved in the analysis of microtremor data in order to produce a shear-wave (Vs) velocity profile and determination of IBC site class.

Results:

Figures 2 and 3 show the shear-wave velocity models for the Tropicana Avenue and Harmon Avenue sites, respectively. The IBC site class value is indicated in the upper right corner of each plot and the shear-wave velocity (Vs) values changes with depth is shown in Tables 1 and 2. Both sites can be classified as Site Class “C” per Table 1613.5.2 in IBC 2006. Both sites show several high velocity caliche layers alternating with lower velocity sand lenses.




Figure 2: Shear-wave velocity (V_s) model obtained from microtremor analysis at the Tropicana Avenue site. Model is characterized by several high velocity caliche layers. The time-averaged velocity value over 100 feet for site class determination per IBC 2006 is shown in the upper right corner. The V_{s100} of 1,466 ft/s places the site in the site class "C" category.




Figure 3: Shear-wave velocity (V_s) model obtained from microtremor analysis at the Harmon Avenue site. Model is characterized by several high velocity caliche layers. The time-averaged velocity value over 100 feet for site class determination per IBC 2006 is shown in the upper right corner. The V_{s100} of 1,400 ft/s places the site in the site class "C" category.



Depth, ft	Vs, ft/s
0	1583
7.81	2441.4
14.32	680.7
17.01	5042.1
22.16	705
26.97	5188
32.85	875.2
41.79	4913.4
48.77	809.8
52.91	4847.8
56.21	1039.5
58.71	1019.4
70.59	1911.8
93.13	1556.8
100	1556.8

Table 2: Shear-wave velocity (Vs) value for each layer in the upper 100 ft for the Tropicana Avenue site.

Depth, ft	Vs, ft/s
0	1641
9.1	4841.2
12.5	722.1
18.6	4857.1
24.1	762.3
31.9	5150.2
36.1	1005.3
47.7	5537.6
53.1	925.1
56.6	1510.2
62.7	1236.1
71.3	1873.3
92.1	1288.7
100	1288.7

Table 2: Shear-wave velocity (Vs) value for each layer in the upper 100 ft for the Harmon Avenue site.