



BRIDGES I-973 N/S
HAZARDOUS MATERIALS SURVEY

BRIDGE INSPECTION AND SURVEY FOR PRESENCE OF
ASBESTOS AND HEAVY METAL(S),
JANUARY 2021

NDOT Hazardous Materials Section, Environmental Division
1263 South Stewart Drive
Carson City, NV 89712

EXECUTIVE SUMMARY

The inspection (survey) for hazardous materials was conducted on bridges I-973 N/S on January 21, 2021 by NDOT personnel from the Hazardous Materials section, of the Environmental Division. These bridges were evaluated for both asbestos containing materials (ACM) and heavy metals in coating materials unless otherwise noted. One suspect metals sample and thirteen suspect asbestos samples were collected with results and considerations summarized below:

- No ACMs were identified
- No heavy metals were found in coating materials.

1.0 INTRODUCTION

NDOT conducted an asbestos survey and screening for metals-based coating materials on the following bridge structure located in Clark county:

- I-973 North (Carp/Elgin Interchange, Northbound I-15)
- I-973 South (Carp/Elgin Interchange, Southbound I-15)

The survey was conducted on January 21, 2021 by NDOT personnel. Due to the similarities between the two bridges; including design, construction materials, date of construction, similar wear patterns and maintenance activities, bridges were surveyed collectively, and findings presented herein, shall apply to both bridges, despite their physical separation.

Suspect Asbestos Containing Material (ACM) were identified and appropriately sampled. Coating materials, if present, were sampled and analyzed for the Resource Recovery and Conservation Act eight (RCRA 8) metals.

Bulk asbestos samples were analyzed by a National Voluntary Laboratory Accredited laboratory by polarized light microscopy (PLM). Metals analysis was conducted by a Nevada Certified Lab. The results of the laboratory analysis are attached as Appendix C and Appendix D, respectively.

2.0 BRIDGE DESCRIPTION

Bridges I-973 North and South were constructed in 2002. Bridges in their entirety are constructed of concrete to include backwall/stem walls, wing walls, parapet/bridge deck overlain with asphaltic concrete. Additionally, coating materials were located throughout the bridges. Two types of fibrous expansion joint material were identified.

3.0 FIELD ACTIVITIES

The survey was conducted by NDOT personnel, appropriately licensed Asbestos and Hazardous Emergency Response Act (AHERA) accredited asbestos inspectors. The survey was conducted in general accordance with the sample collection protocols established in EPA regulation 40 CFR 763. A summary of the survey activities performed is discussed below. Copies of AHERA certifications and licenses for NDOT personnel conducting the survey are provided as Appendix E.

3.1 Visual and Physical Assessment

Survey activities began with a visual observation of the structures to identify homogeneous areas of suspect ACM and presence of coating materials. A physical assessment of each homogeneous area of suspect ACM was conducted to assess the friability and condition of the materials.

The homogeneous areas identified during the visual survey, the presence of coating materials, and sample identifiers are summarized in Table 1.

Table 1 - Bridge Component Descriptions

Homogeneous Area	Description	Sample IDs
A	bridge backwall / stem wall	STEM-1, STEM-2, STEM-3
B	wing wall	WW-1, WW-2, WW-3
C	parapet / bridge deck	PARA-1, PARA-2, PARA-3
D	fibrous expansion joint	EXP-1
E	fibrous expansion joint	EXP-2
F	grey texture coating	TXT-1
G	grey texture (cementous)	TXT-2 ⁽¹⁾

notes: (1) cementous texture, texturing only analyzed for asbestos.

3.2 Sample Collection

Based on results of the visual observation, bulk samples of suspect ACM and coating materials were collected in general accordance with AHERA sampling protocols. Representative samples of suspect materials were collected in each homogeneous area. Samples were placed in new sealable containers and labeled with unique sample numbers.

3.3 Sample Analysis

Bulk samples of ACM were submitted under chain of custody to Asbestos TEM Laboratories for analysis by PLM. The percentage of asbestos, where applicable, was determined by microscopic visual estimation. Coating material samples were also submitted to Alpha Analytical and analyzed for heavy metals using EPA 6020 test method.

A discussion of suspect ACM and suspect metals-based coating samples collected during the survey and findings are included in Section 6.0.

4.0 PLAN REVIEW

Review of original design plans was not necessary.

5.0 REGULATORY OVERVIEW

5.1 Asbestos Regulations

NESHAP (40 CFR Part 61, Subpart M) regulates asbestos fiber emissions and asbestos waste disposal practices. It also requires the identification and classification of existing building materials prior to demolition or renovation activity. Under NESHAP, asbestos-containing building materials are classified as either friable, Category I non-friable, or Category II non-friable ACM. Category I non-friable ACM includes packings, gaskets, resilient floor coverings and asphalt roofing products containing more than 1% asbestos. Category II non-friable ACM are any materials other than Category I materials that contain more than 1% asbestos.

Friable ACM, Category I and Category II non-friable ACM which are in poor condition and have become friable or which will be subjected to drilling, sanding, grinding, cutting or abrading and

which could be crushed or pulverized during anticipated renovation or demolition activities are considered Regulated ACM (RACM).

5.2 Coating Material and Lead Based Paint Regulations

Lead-based paint (LBP) is defined as a surface coating or paint containing lead in excess of 0.5% (5000 mg/Kg) by weight (EPA Toxic Substance Control Act, Section 401).

Under EPA regulations heavy metal impacted wastes generated during abatement activities are handled as either a solid waste or a hazardous waste, depending on the concentration of each of the metal(s) and the method of coating material removal.

6.0 FINDINGS AND RECOMMENDATIONS

6.1 Suspect Asbestos Containing Materials

A total of 13 bulk samples were collected from seven homogeneous areas of suspect ACM. No Asbestos Containing Materials were identified.

A bridge Location Map is included in Appendix A. A photographic log showing homogenous areas is presented in Appendix B. Asbestos analytical results are included in Appendix C. A summary of the suspect ACMs identified is provided in Table 2.

Table 2 – Summary of Suspected ACM

Homogeneous Sampling Area	Sample Number	Material Description/Sample Location	Asbestos Results ⁽¹⁾ , %	NESHAAP Category ⁽²⁾	Friability ⁽³⁾
A	STEM-1	bridge backwall / stem wall	Not detected	N/A	non-friable
	STEM-2				
	STEM-3				
B	WW-1	wing wall	Not detected	N/A	non-friable
	WW-2				
	WW-3				
C	PARA-1	parapet / bridge deck	Not detected	N/A	non-friable
	PARA-2				
	PARA-3				
D	EXP-1	fibrous expansion joint	Not detected	N/A	friable
E	EXP-2	fibrous expansion joint	Not detected	N/A	friable
F	TXT-1	grey texture coating	Not detected	N/A	non-friable
G	TXT-2	grey texture (cementous)	Not detected	N/A	non-friable

notes: (1) PLM unless otherwise noted.

(2) NESHAAP category I, category II, RACM, or (N/A) not applicable.

(3) Friable materials are those that, when dry, may be crumbled, pulverized or reduced to powder by hand pressure.

Additional suspect materials, other than those identified during the survey, could exist within the structures in areas not accessible to the inspector at the time of the survey. Should suspect materials other than those identified during this survey be uncovered during the renovation/demolition process, those materials should be assumed to be ACM until sampling and analysis can confirm or refute this assumption.

6.2 Coating Materials

One composite texture sample from the white cementous coating material applied to the concrete parapets identified as “973 Paint” was collected for analysis. This composite sample was analyzed for total arsenic, barium, cadmium, chromium, lead, selenium, silver, and mercury metals. No metals were detected above method limits.

Cementous grey texturing found throughout the bridges as well, while sampled for asbestos, was not sampled for heavy metals due cementous nature of coating material. Experience has shown that method to remove coating material, results in a disproportional concentration of concrete to coating materials. Consequently, heavy metal detections, if found, are more a reflection of the concrete matrix than coating material.

Analytical results are included in Appendix D and laboratory results are summarized in Table 3.

Table 3 – Summary of Coating Material

Sample Identification	Material Description/Sample Location	Heavy Metal Results ⁽¹⁾ , mg/Kg							
		As	Ba	Cd	Cr	Pb	Se	Ag	Hg
973 Paint	grey coating material	nd	nd	nd	nd	nd	nd	nd	nd

notes: (1) EPA test method 6020.

nd – not detected above method limits.

6.3 Recommendations

No ACMs were identified, and no heavy metals were detected above method limits in coating materials. Consequently, there are no recommendations at this time.

Appendix A
Bridge Location Map

Bridges I-973 N/S
Carp/Elgin Interchange, I-15
Clark County, Nevada



Appendix B
Bridge Photo Log

PHOTOGRAPHIC DOCUMENTATION

**NDOT Hazardous Materials Survey
Bridge I-973 N/S
I-15
Clark County, Nv**

PHOTO 1

DATE:
1/21/2021

DIRECTION:
North

TAKEN BY:
Brian Reed

DESCRIPTION:
Bridges I-973
North & South.



PHOTO 2

DATE:
1/21/2021

DIRECTION:
South

TAKEN BY:
Brian Reed

DESCRIPTION:
Stemwall, and
wingwall.



PHOTOGRAPHIC DOCUMENTATION

**NDOT Hazardous Materials Survey
Bridge I-973 N/S
I-15
Clark County, Nv**

PHOTO 3

DATE:
1/21/2021

DIRECTION:
West

TAKEN BY:
Brian Reed

DESCRIPTION:
Parapet, wingwall,
and mainlane.



PHOTO 4

DATE:
1/21/2021


DIRECTION:
North

TAKEN BY:
Brian Reed

DESCRIPTION:
Bridge I-973 S.



Appendix C
Asbestos Sample(s)
Analytical Results



ASBESTOS TEM LABORATORIES, INC.

**EPA Method 600/R-93/116
Polarized Light Microscopy
Analytical Report**

Report No. 143628

1350 Freeport Blvd., Unit 104
Sparks, NV 89431
(775) 359-3377
FAX (775) 359-2798

Main Office Located At:
3431 Ettie Street Oakland, CA 94608
Ph. (510) 704-8930 Fax (510) 704-8929



ASBESTOS TEM LABORATORIES, INC



NVLAP Lab Code 200104-0

Jan-29-21

Robert Piekarz
Nevada Department of Transportation
1263 South Stewart Street
Carson City, NV 89712

RE: LABORATORY JOB # 9092-00051
Polarized light microscopy analytical results for 13 bulk sample(s).
Job Site: D1 I-15
Job No.:
Report No.: 143628

Enclosed please find the bulk material analytical results for one or more samples submitted for asbestos analysis. The analyses were performed in accordance with EPA Method 600/R-93/116 or 600/M4-82-020 for the determination of asbestos in bulk building materials by polarized light microscopy (PLM). Please note that while PLM analysis is commonly performed on non-friable and fine grained materials such as floor tiles and dust, the EPA method recognizes that PLM is subject to limitations. In these situations, accurate results may only be obtainable through the use of more sophisticated and accurate techniques such as transmission electron microscopy (TEM) or X-ray diffraction (XRD).

Prior to analysis, samples are logged-in and all data pertinent to the sample recorded. The samples are checked for damage or disruption of any chain-of-custody seals. A unique laboratory ID number is assigned to each sample. A hard copy log-in sheet containing all pertinent information concerning the sample is generated. This and all other relevant paper work are kept with the sample throughout the analytical procedures to assure proper analysis.

Each sample is opened in a class 100 HEPA negative air hood. A representative sampling of the material is selected and placed onto a glass microscope slide containing a drop of refractive index oil. The glass slide is placed under a polarizing light microscope where standard mineralogical techniques are used to analyze and quantify the various materials present, including asbestos. The data is then compiled into standard report format and subjected to a thorough quality assurance check before the information is released to the client.

Please note all samples will be held for 3 months from the date of receipt unless otherwise requested by client.

Sincerely Yours,

Laboratory Analyst
ASBESTOS TEM LABORATORIES, INC.

--- These results relate only to the samples tested and must not be reproduced, except in full, with the approval of the laboratory. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. ---



NVLAP Lab Code 200104-0

POLARIZED LIGHT MICROSCOPY ANALYTICAL REPORT

EPA Method 600/R-93/116 or 600/M4-82-020

Page: 1 of 2

Contact: Robert Piekarz	Samples Indicated: 13	Report No. 143628
Address: Nevada Department of 1263 South Stewart Street Carson City, NV 89712	Reg. Samples Analyzed: 13	Date Submitted: Jan-22-21
	Split Layers Analyzed: 0	Date Reported: Jan-29-21
Job Site / No. D1 I-15		

SAMPLE ID	ASBESTOS % TYPE	OTHER DATA	DESCRIPTION
		1) Non-Asbestos Fibers 2) Matrix Materials 3) Date/Time Collected 4) Date Analyzed	FIELD LAB
STEM-1 Lab ID # 9092-00051-001	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq	Grey concrete - stem wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
STEM-2 Lab ID # 9092-00051-002	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - stem wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
STEM-3 Lab ID # 9092-00051-003	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - stem wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
WW-1 Lab ID # 9092-00051-004	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - wing wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
WW-2 Lab ID # 9092-00051-005	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - wing wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
WW-3 Lab ID # 9092-00051-006	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - wing wall
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
PARA-1 Lab ID # 9092-00051-007	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - parapet
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
PARA-2 Lab ID # 9092-00051-008	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - parapet
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
PARA-3 Lab ID # 9092-00051-009	None Detected	1) None Detected 2) 99-100% Qtz, Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey concrete - parapet
		3) 1-21-21 4) Jan-29-21	Concrete-Grey
EXP-1 Lab ID # 9092-00051-010	None Detected	1) 20-30% Cellulose 2) 70-80% Opq, Bndr	Brown fiberboard - expansion joints
		3) 1-21-21 4) Jan-29-21	Fiberboard-Brown

Limit of quantitation of method is estimated to be 1% asbestos using a visual area estimation technique. Split samples are inhomogeneous.

Laboratory Analyst
Greg Hanes



NVLAP Lab Code 200104-0

POLARIZED LIGHT MICROSCOPY ANALYTICAL REPORT

EPA Method 600/R-93/116 or 600/M4-82-020

Page: 2 of 2

Contact: Robert Piekarz	Samples Indicated: 13	Report No. 143628
Address: Nevada Department of 1263 South Stewart Street Carson City, NV 89712	Reg. Samples Analyzed: 13	Date Submitted: Jan-22-21
	Split Layers Analyzed: 0	Date Reported: Jan-29-21
Job Site / No. D1 I-15		

SAMPLE ID	ASBESTOS % TYPE	OTHER DATA	DESCRIPTION
		1) Non-Asbestos Fibers 2) Matrix Materials 3) Date/Time Collected 4) Date Analyzed	FIELD LAB
EXP-2 Lab ID # 9092-00051-011	None Detected	1) 20-30% Cellulose 2) 70-80% Opq, Bndr <i>Fib. Op. Prop. Same as in</i>	Brown fiberboard - expansion joints
		3) 1-21-21 4) Jan-29-21	Fiberboard-Brown
TXT-1 Lab ID # 9092-00051-012	None Detected	1) None Detected 2) 99-100% Calc, Opq	Grey texture - throughout bridge
		3) 1-21-21 4) Jan-29-21	Texture-Grey
TXT-2 Lab ID # 9092-00051-013	None Detected	1) None Detected 2) 99-100% Calc, Opq <i>Fib. Op. Prop. Same as in</i>	Grey texture - throughout bridge
		3) 1-21-21 4) Jan-29-21	Texture-Grey
Lab ID #		1)	
		2)	
Lab ID #		3)	
		4)	
Lab ID #		1)	
		2)	
Lab ID #		3)	
		4)	
Lab ID #		1)	
		2)	
Lab ID #		3)	
		4)	
Lab ID #		1)	
		2)	
Lab ID #		3)	
		4)	

Limit of quantitation of method is estimated to be 1% asbestos using a visual area estimation technique. Split samples are inhomogeneous.

Laboratory Analyst
Greg Hanes

Survey Data

Inspectors: Brian Reed/Robert Plekarz		Project Name: I 973 - Bridge		Project Number:		Date Sampled: 1/21/21		
Phone: 775-888-7892		Fax: 775-888-7104		Analysis Type: Asbestos		Air		
Turn-A-Round Time: Rush 24-Hour		Requests: Verbal		Fax		Test to First Positive:		
Lab #	Sample ID	Material Description	Sample Location	Location of Materials	Quantity	Condition	Friable	Asbestos %
1	Stem-1	grey concrete	Stem wall	Bridge I-973 N/S	1	G	N	
2	Stem-2				1	G	N	
3	Stem-3				1	G	N	
4	WW-1		wing wall		1	G	N	
5	WW-2				1	G	N	
6	WW-3				1	G	N	
7	Para-1				1	G	N	
8	Para-2				1	G	N	
9	Para-3				1	G	N	
10	Exp-1	Brown Fiberboard	Expansion Joints		1	G	N	

Comments/Additional Information

MATERIAL	CONDITION	UNITS	ASBESTOS %
VT - Vinyl Tile M - Mastic CJM - Cove Base Mastic AT - Acoustical Tile SA - Spray Acoustic W - Wall P - Plaster	G - Good D - Damaged SD - Significant Damage	LF - Linear Feet SF - Square Feet CF - Cubic Feet	A - Asbestos C - Chrysotile NDA - No Asbestos Detected Assumed ACM - No Samples Taken

Relinquished By: Andrew Struss Date/Time: 1/22/21 10:55
 Received By: ATEM

Survey Data

Inspectors: Brian Reed/Robert Piekarz		Project Name: Bridge I-973		Project Number:		Date Sampled: 1/21/21			
Phone: 775-888-7892 Fax: 775-888-7104		Project Location: D7 I-15		Analysis Type: Asbestos		Air Bulk			
Turn-A-Round Time: Rush 24-Hour 2 Day		Requests: Verbal		Fax		Test to First Positive:			
Lab #	Sample ID	Material Description	Sample Location	Location of Materials	Quantity	Condition	Friable	Yes	Asbestos %
1	Exp-2	Brown Fiberglass	Expansion Joints	Bridge I-973 NB	1	G	N		
2	TX6-1	Grey Texture	throughout Bridge		1	G	N		
3	TX6-2				1	G	N		
4									
5									
6									
7									
8									
9									
10									

Comments/Additional Information

MATERIAL	CONDITION	UNITS	ASBESTOS %
PF1 - Pipe Fitted Insulation	G - Good	LF - Linear Feet	A - Asbestos Asbestos
PR1 - Pipe Run Insulation	D - Damaged	SF - Square Feet	C - Chrysotile Asbestos
DI - Duct Insulation	SD - Significant Damage	CF - Cubic Feet	NDA - No Asbestos Detected
T - Tank Insulation			Assumed ACM - No Samples Taken
EJ - Expansion Joint			
BI - Boiler Insulation			
P - Plaster			
GA - Gasket			
D - Debris			
ISA - Thermal System Insulation			
R - Roof			
DW - Drywall			
JC - Joint Compound			

Relinquished By: Brian Reed Date/Time: 1/22/21 10:55
 Relinquished By: _____ Date/Time: _____
 Received By: _____ Received By: _____

Appendix D
Material Coating Sample(s)
Analytical Results



Alpha Analytical, Inc.
255 Glendale Ave, #21
Sparks, Nevada 89431
TEL: (775) 355-1044 FAX: (775) 355-0406
Website: www.alpha-analytical.com

February 02, 2021

Robert Piekarz
Nevada DOT Environmental (NDOT)
1263 S. Stewart St.
Carson City, NV 89712
TEL: (775) 888-7692
FAX: (775) 888-7104

RE: Bridges D1

Order No.: NDO2101114

Dear Robert Piekarz:

The result of this report apply to the sample(s) as received.

There were no problems with the analytical events associated with this report unless noted.

Quality control data is within laboratory defined or method specified acceptance limits except if noted.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

A handwritten signature in black ink that reads "Roger Scholl".

Roger Scholl
Laboratory Director
255 Glendale Ave, #21
Sparks, Nevada 89431



Alpha Analytical, Inc.
 255 Glendale Ave, #21
 Sparks, Nevada 89431
 TEL: (775) 355-1044 FAX: (775) 355-0406
 Website: www.alpha-analytical.com

Analytical Report

WO#: NDO2101114

Report Date: 2/2/2021

CLIENT: Nevada DOT Environmental (NDOT)

Collection Date: 1/21/2021 9:00:00 AM

Project: Bridges D1

Lab ID: 2101114-06

Matrix: OTHER

Client Sample ID: 973 Paint

Analyses	Result	RL	Qual	Units	Date Analyzed	Method
Chromium (Cr)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Arsenic (As)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Selenium (Se)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Silver (Ag)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Cadmium (Cd)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Barium (Ba)	ND	1.0		mg/L	1/26/2021	Metals by EPA 6020
Mercury (Hg)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020
Lead (Pb)	ND	0.10		mg/L	1/26/2021	Metals by EPA 6020

NOTES:

This analysis was performed on a TCLP extract.



Alpha Analytical, Inc.
 255 Glendale Ave, #21
 Sparks, Nevada 89431
 TEL: (775) 355-1044 FAX: (775) 355-0406
 Website: www.alpha-analytical.com

QC SUMMARY REPORT

WO#: 2101114

02-Feb-21

Client: Nevada DOT Environmental (NDOT)

Project: Bridges D1

TestCode: METALS_T_6020

Sample ID: MB-12294	SampType: MBLK	TestCode: METALS_T_6	Units: mg/L
Client ID: PBW	Batch ID: 12294	TestNo: E200.8	
Prep Date: 1/26/2021	RunNo: 10900	SeqNo: 309185	
Analysis Date: 1/26/2021			

Analyte	Result	PQL	SPK Value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chromium (Cr)	ND	0.01									
Arsenic (As)	ND	0.005									
Selenium (Se)	ND	0.005									
Silver (Ag)	ND	0.005									
Cadmium (Cd)	ND	0.002									
Barium (Ba)	ND	0.005									
Mercury (Hg)	ND	0.001									
Lead (Pb)	ND	0.005									

Sample ID: LCS-D-12294	SampType: LCS-D	TestCode: METALS_T_6	Units: mg/L
Client ID: LCSS02	Batch ID: 12294	TestNo: E200.8	
Prep Date: 1/26/2021	RunNo: 10900	SeqNo: 309187	
Analysis Date: 1/26/2021			

Analyte	Result	PQL	SPK Value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chromium (Cr)	0.252	0.01	0.25	0	101	79.51	120.49	0.243	3.7	20	
Arsenic (As)	0.258	0.005	0.25	0	103	79.51	120.49	0.244	5.5	20	
Selenium (Se)	0.252	0.005	0.25	0	101	79.51	120.49	0.237	6	20	
Silver (Ag)	0.239	0.005	0.25	0	95.7	79.51	120.49	0.232	3	20	
Cadmium (Cd)	0.239	0.002	0.25	0	95.7	79.51	120.49	0.235	1.9	20	
Barium (Ba)	0.243	0.005	0.25	0	97.4	79.51	120.49	0.231	5.4	20	
Mercury (Hg)	0.00442	0.001	0.005	0	88.3	79.51	120.49	0.00412	7	20	
Lead (Pb)	0.237	0.005	0.25	0	94.9	79.51	120.49	0.224	5.8	20	

Sample ID: LCS-12294	SampType: LCS	TestCode: METALS_T_6	Units: mg/L
Client ID: LCSW	Batch ID: 12294	TestNo: E200.8	
Prep Date: 1/26/2021	RunNo: 10900	SeqNo: 309186	
Analysis Date: 1/26/2021			

Analyte	Result	PQL	SPK Value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chromium (Cr)	0.243	0.01	0.25	0	97.1	79.51	120.49				
Arsenic (As)	0.244	0.005	0.25	0	97.6	79.51	120.49				
Selenium (Se)	0.237	0.005	0.25	0	94.9	79.51	120.49				
Silver (Ag)	0.232	0.005	0.25	0	92.8	79.51	120.49				
Cadmium (Cd)	0.235	0.002	0.25	0	93.9	79.51	120.49				
Barium (Ba)	0.231	0.005	0.25	0	92.3	79.51	120.49				
Mercury (Hg)	0.00412	0.001	0.005	0	82.4	79.51	120.49				
Lead (Pb)	0.224	0.005	0.25	0	89.5	79.51	120.49				

Qualifiers: B Analyte detected in the associated Method Blank
 ND Not Detected at the Reporting Limit
 R RPD outside accepted recovery limits
 S Spike Recovery outside accepted recovery limit



Alpha Analytical, Inc.
 255 Glendale Ave, #21
 Sparks, Nevada 89431
 TEL: (775) 355-1044 FAX: (775) 355-0406
 Website: www.alpha-analytical.com

QC SUMMARY REPORT

WO#: 2101114

02-Feb-21

Client: Nevada DOT Environmental (NDOT)

Project: Bridges D1

TestCode: METALS_T_6020

Sample ID: LCS-12294	SampType: LCS	TestCode: METALS_T_6	Units: mg/L								
Client ID: LCSW	Batch ID: 12294	TestNo: E200.8									
Prep Date: 1/26/2021	RunNo: 10900	SeqNo: 309186									
Analysis Date: 1/26/2021											
Analyte	Result	PQL	SPK Value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

- Qualifiers:**
- B Analyte detected in the associated Method Blank
 - ND Not Detected at the Reporting Limit
 - R RPD outside accepted recovery limits
 - S Spike Recovery outside accepted recovery limit



Alpha Analytical, Inc.
255 Glendale Ave, #21
Sparks, Nevada 89431
TEL: (775) 355-1044 FAX: (775) 355-0406
Website: www.alpha-analytical.com

Definition Only

WO#: 2101114
Date: 2/2/2021

Definitions:

ND = Not Detected

C = Reported concentration includes additional compounds uncharacteristic of common fuels and lubricants.

D = Reporting Limits were increased due to high concentrations of non-target analytes.

H = Reporting Limits were increased due to the hydrocarbons present in the sample.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

K = DRO concentration may include contributions from lighter-end hydrocarbons (e.g. gasoline) that elute in the DRO range.

L = DRO concentration may include contributions from heavier-end hydrocarbons (e.g. motor oil) that elute in the DRO range.

O = Reporting Limits were increased due to sample foaming.

V = Reporting Limits were increased due to high concentrations of target analytes.

X = Reporting Limits were increased due to sample matrix interferences.

Z = DRO concentration may include contributions from lighter-end (e.g. gasoline) and heavier-end (e.g. motor oil) hydrocarbons that elute in the DRO range.

S50 = The analysis of the sample required a dilution such that the surrogate concentration was diluted below the laboratory acceptance criteria. The laboratory control sample was acceptable.

S51 = Surrogate recovery could not be determined due to the presence of co-eluting hydrocarbons.

S52 = Surrogate recovery was above laboratory acceptance limits. Probable matrix effect.

S53 = Surrogate recovery was below laboratory acceptance limits. Probable matrix effect.

S54 = Surrogate recovery was below laboratory acceptance limits.

S55 = Surrogate recovery was above laboratory acceptance limits.

Report CC's Dan Twichell
Robert Piekarz

WORKORDER SUMMARY

NV

WorkOrder: NDO2101114
Report Due By: 05-Feb-21
EDD Required: NO

Alpha Analytical, Inc.

255 Glendale Ave, #21 Sparks, Nevada 89431
TEL: (775) 355-1044 FAX: (775) 355-0406

Report Attention: Robert Piekarz

Client:


Nevada DOT Environmental (NDOT)
1263 S. Stewart St.
Carson City, NV 89712

TEL: 7758887692
FAX: 7758887104
ProjectNo: Bridges D1

Date Received: 22-Jan-21

Alpha Sample ID	Client Sample ID	Matrix	Collection Date	No. of Bottles			Requested Tests						Sample Remarks	
				Alpha	Sub	TAT	METALS_T_60 20							
NDO2101114-01	Abt Paint-1412	OTHER	1/20/2021 2:00:00 PM	1	0	10	A - TCLP_8							
NDO2101114-02	Texture-412	OTHER	1/20/2021 2:10:00 PM	1	0	10	A - TCLP_8							
NDO2101114-03	I-Beam Paint-1443	OTHER	1/20/2021 3:30:00 PM	1	0	10	A - TCLP_8							
NDO2101114-04	Bridge Paint-1443	OTHER	1/20/2021 3:45:00 PM	1	0	10	A - TCLP_8							
NDO2101114-05	Column Paint-1443	OTHER	1/20/2021 4:00:00 PM	1	0	10	A - TCLP_8							
NDO2101114-06	973 Paint	OTHER	1/21/2021 9:00:00 AM	1	0	10	A - TCLP_8							
NDO2101114-07	1109 Paint	OTHER	1/21/2021 10:30:00 AM	1	0	10	A - TCLP_8							

Comments: Paint chips

Signature	Print Name	Company	Date/Time
 Logged in by:	Daija Nordyke	Alpha Analytical, Inc.	1.22.21 11:35

NOTE: Samples are discarded 60 days after sample receipt unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.

Billing Information:

Company: Nevada Department of Transportation
 Attn: Robert Piekarz
 Address: 1263 S. Stewart Street
 City, State, Zip: Carson City, NV 89712
 Phone Number: 775-888-7692 Fax: _____



Alpha Analytical, Inc.

Main Laboratory 255 Glendale Ave, Suite 21 Sparks, NV 89431

Phone: 775-355-1044

Fax: 775-355-0406

Satellite Service Centers:

Northern CA: 9891 Horn Road, Suite C, Rancho Cordova, CA 95827

Phone: 916-366-9089

Southern NV: 6255 McLeod Ave, Suite 24, Las Vegas, NV 89120

Phone: 702-736-7522

Southern CA: 1007 E. Dominguez St., Suite O, Carson, CA 90746

Phone: 310-803-7761

Consultant/ Client Info:		Job and Purchase Order Info:		Report Attention/Project Manager:		QC Deliverable Info:	
Company:	Same As Above	Job #:	Not Applicable	Name:	Robert Piekarz	EDD Required?	Yes <input checked="" type="radio"/> No
Address:		Job Name:	Bridges #117 D1	Email Address:	rpiekarz@dot.state.nv.us	EDF Required?	Yes <input type="radio"/> No
City, State, Zip:		P.O. #:		Phone #:	775-888-7692	Global ID:	
				Cell #:		Data Validation Level:	III or IV

Samples Collected from which State? (circle one) AZ CA <u>NV</u> WA ID OR DOD Site Other										Analysis Requested										Remarks
Time Sampled (HHMM)	Date Sampled (MMDD)	Matrix* (See Key Below)	Lab ID Number (For Lab Use Only)	Sample Description	TAT	Field Filtered?	# Containers** (See Key Below)													
1400	1/20	OT	NDO2101114-01	Abt Paint - 1412	Stnd	N	1-OT	X												
1410	1/20	OT	02	Texture - 1412	Stnd	N	1-OT	X												
1530	1/20	OT	03	I-Beam Paint - 1449 1443	Stnd	N	1-OT	X												I-Beam Paint - 1443
1545	1/20	DT	04	Bridge Paint - 1449 1443	Stnd	N	1-OT	X												
1600	1/20	OT	05	Coldman Paint - 1449 1443	Stnd	N	1-OT	X												
0900	1/21	OT	06	973 Paint	Stnd	N	1-OT	X												
1030	1/21	OT	07	1109 Paint	Stnd	N	1-OT	X												

ADDITIONAL INSTRUCTIONS:

I (field sampler) attest to the validity and authenticity of this sample(s). I am aware that tampering with or intentionally mislabeling the sample location, date or time of collection is considered fraud and may be grounds for legal action. NAC 445.0636 (c) (2).

Relinquished by (Signature/Affiliation):	Date: 1/22/21	Time: 1045	Received by (Signature/Affiliation):	Date: 1.22.21	Time: 10:45
Relinquished by (Signature/Affiliation):	Date:	Time:	Received by (Signature/Affiliation):	Date:	Time:
Relinquished by (Signature/Affiliation):	Date:	Time:	Received by (Signature/Affiliation):	Date:	Time:

* Key: AQ - Aqueous WA - Waste OT - Other ** : L - Liter V - VOA S - Soil Jar O - Orbo T - Tedlar B - Brass P - Plastic OT - Other
 NOTE: Samples are discarded 60 days after sample receipt unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense. The report for the analysis of the above samples is applicable only to those samples received by the laboratory with this COC. The liability of the laboratory is limited to the amount paid for the report.

Appendix E
Inspector Certifications
and
Licenses

mm


STATE OF NEVADA
DEPARTMENT OF BUSINESS AND INDUSTRY
DIVISION OF INDUSTRIAL RELATIONS
Occupational Safety and Health Administration
Asbestos Control Program

Certifies That Robert Piekarz
State of Nevada-DOT
is Licensed As Asbestos Abatement Consultant

License No. IJ-1049

Expiration Date 11/24/2021

Signature Of Licensee _____



STATE OF NEVADA
DEPARTMENT OF BUSINESS AND INDUSTRY
DIVISION OF INDUSTRIAL RELATIONS
Occupational Safety and Health Administration
Asbestos Control Program

mm

Certifies That Robert Piekarz
State of Nevada-DOT
is Licensed As Asbestos Abatement Consultant

License No. IJ-1049 Expiration Date 11/24/2021

Signature Of Licensee _____

M & C Environmental Training

Asbestos Inspector
Refresher Training Course

Robert Piekarz

Has successfully completed the Asbestos Inspector Refresher course approved by the California Division of Occupational Safety and Health for purposes of certification required by Title 8, Article 2.7, Chapter 3.2, Section 341.16 and the accreditation required under the Toxic Substances Control Act, Title II. Conducted by M&C Environmental Training Inc., P.O. Box 6419, Concord, California Tel. # (510 499-5646

Course Approval Number: CA-003-06

Location: Concord, California

Expiration: November 24, 2021

Dates: November 24, 2020

Director of Training: John McGinnis



Certificate Number 48309 IR

M & C Environmental Training

Asbestos Management Planner Refresher Training Course

Robert Piekarz


Has successfully completed the Asbestos Management Planner Refresher course approved by the California Division of Occupational Safety and Health for purposes of certification required by Title 8, Article 2.7, Chapter 3.2, Section 341.16 and the accreditation required under the Toxic Substances Control Act, Title II. Conducted by M&C Environmental Training Inc., P.O. Box 6419, Concord, California. Tel. # (510) 499 - 5646

Course Approval Number: CA-003-08

Location: Concord, California

Dates: November 24, 2020

Director of Training: John McGinnis



Expiration: November 24, 2021

Certificate Number **48327 PR**