For continuation see below
Provide a NB Full Auxiliary Lane From Charleston to Eastern With Dual Lane Exit at Eastern
Provide a SB Full Auxiliary Lane From Eastern to Charleston With Dual Lane Exit at Charleston
N. MOJAVE RD.
NB. I-515
SB. I-515
STEWART AVE.
Widen NB Charleston On Ramp to Three Lanes Storage
Provide a NB Full Auxiliary Lane From Charleston to Eastern With Dual Lane Exit at Eastern
N. SANDHILL RD.
E. CHARLESTON BLVD.
N. HONOLULU ST.
95
93
515
Widen Charleston NB Off-Ramp ( With Dual Lane Exit)
Provide a SB Full Auxiliary Lane from Eastern to Charleston With Dual Lane Exit at Charleston
Increase storage on Charleston SB Off-Ramp
OLIVE ST.
S. SANDHILL RD.
N. PECOS RD.
For continuation see above
Provide Deceleration Lane (Exit Lane) for SB Exit at Charleston and Provide Dual Exit
PROPOSED IMPROVEMENTS
Roadway
Bridge Structure
0 100 200 400
SCALE: 1"=100'
PRELIMINARY
SUBJECT TO REVISION
March 31, 2016
I-515 ALTERNATIVES DEVELOPMENT STUDY
PUBLIC INFORMATION MEETING
March 31, 2016
All information presented is preliminary and subject to revision
NEVADA DOT
SAFE AND CONNECTED
INTERSTATE 515
Moving forward together